

BOQ (FOR REFERENCE PURPOSE ONLY)-Construction of RRM wall at loc no. 60 of 400 kV Allahabad-Kanpur(GIS) transmission line under Prayagraj TLM

Sl.No.	Activity Description	Item Description	Unit	Quantity
1	TWR FOOTING PROT-RUBBLE STONE	Random rubble stone masonry including excavation (1:5 cement mortar).	Cum	466.367
2	TWR FOOTING PROT-BACKFILLING/GAP LEVEL	Backfilling and gap levelling of volume enclosed by revetment.	Cum	281.827
3	LEAN CONCRETE (1:3:6)	Lean concrete (1:3:6)	Cum	12.40
4	TWR FOOTING PROT-M15 CONCRETE FOR COVER	M15 (1:2:4) mixed concrete for top seal cover of revetment	Cum	2.31