TECHNICAL SPECIFICATION OF SOLAR PHOTOVOLTAIC POWER PLANT

1. Solar CAR PARKING SHED with minimum 3.0 m distance between 2 vertical poles having minimum head room clearance of 3.0 meter above the ground level.
2. Supplying, Installation, Testing and Commissioning of on-grid Solar Photovoltaic Power Plant conforming to various applicable standards BIS, IEC, MNRE guidelines, the Central Electricity Authority Regulations and CPWD Specifications as amended up to date, consisting of Mono/Poly Crystalline silicon solar cells module, net metering facility, necessary control, protections, earthing, cabling, mounting structure, junction boxes, power conditioning units, Real time online web interfaced Data Monitoring System, Distribution panels, grid connecting arrangement, conduits, pipes, cable trays and other accessories etc. as required.
3. High Energy Efficiency Solar Photovoltaic Module of capacity 330 Wp or above, manufactured in India, conforming to IS 14286/IEC 61215, IS/IEC 61730 Part-1, IS/IEC 61730-Part-2. Solar Photovoltaic Module conversion efficiency shall not be less than 23% at STC with temperature coefficient of Pmax better than -0.30% per 0C. PV modules used in solar power plants/ systems must be warranted for their output peak watt capacity, which should not be less than 90% at the end of 10 years and 80% at the end of 25 years. Solar Modules shall be designed to operate in relative humidity upto 100% with temperature between -10 0C and +85 0C. Further, each PV module used in any solar power project must have Radio frequency identification tag with information such as name of manufacturer, month and year of manufacturing, country of origin (separately for Solar cell and module), I-V curve, Unique Serial No and Model No of the module, Wattage, Im, Vm and FF, name of test lab issuing IEC certificate.
4. Power Conditioning Unit (PCU) of 350-800 V DC Input voltage range and 415 V AC, three phase, 4 wire, 50Hz +/- 2.5 Hz, output voltage suitable to generate AC with a variation of 10% at nominal voltage. Power with efficiency not less than 97%, total harmonic distortion less than 3% and suitable for ambient temperature from 0 to 50 0C, Minimum IP-65 for outdoor and Minimum IP 21 for indoor, Built-in meter and data logger, MPPT, switching devices IGBT/MOSFETs and controller Microprocessor /DSP. PCU/inverter shall be capable of complete automatic operation including wake-up, synchronization & shutdown. The PCU shall be able to withstand unbalanced

डेटा वर्गीकरण : नियंत्रित/CONTROLLED

load conforming to IEC standard with shutdown/standby mode. It must be provided with grid islanding along with manual disconnect pole isolation switch besides automatic disconnection. Minimum protections: Mains Under / Over Voltage, Over current, Over/Under grid frequency, Over temperature, Surge voltage induced at output due to external source, Short-circuit, Lightening, Anti Islanding (for grid synch. Mode) and other protections as per applicable standards. LCD/LED display of minimum parameters: DC input voltage, DC current, AC Voltage and current (all 3 phases, in case of 3 phase), Instantaneous & cumulative AC output power, Daily DC energy produced and other parameters applicable standard. Communication interface RS 485 / RS 232.

5. Module mounting structure: The roof top solar plant generation units shall be installed by using supporting Aluminium/Galvanized MS structure (mass of zinc coating shall be as per IS4759) having minimum head room clearance of 3.0 meter above the terrace level / ground level. The mounting structure would be designed to sustain wind load and seismic parameter of the site of installation. All the structure shall be design as per applicable BIS code and the material shall also confirm the applicable BIS Code. Structural material shall be corrosion resistant and electrolytically compatible with the materials used in the module frame, its fasteners, nuts and bolts. The suitable arrangements for maintenance and cleaning shall be provided.
6. Real time online web interfaced Data Monitoring System complete with accessories for various parameters such as Solar Irradiance, temperature, AC Output Voltage and current, Output Power, Power factor, DC Input Voltage and Current, Time Active, Time disabled, Time Idle, Power produced and other parameters as per standard practices.
7. Array junction box & Main junction box with IP 65 protection and termination arrangement for incoming and outgoing cable along with glands, lugs and other accessories etc. as required. Each junction box shall be made of GRP/FRP/Powder Coated Aluminium /cast Aluminium alloy with full dust, water & vermin proof arrangement with High quality Suitable capacity Metal Oxide Varistors (MOVs) (semiconductor diode with resistant applied voltage)/ surge arrestors and suitable Reverse Blocking Diodes, isolation switches isolate the DC input to Inverter, copper bus bar etc.
8. Lightning, surge voltage protection, earthing protection and grid islanding.
9. Cables: Connections & Interconnections by required size IR/UV protected XLPE insulated copper conductor 1.1 kV grade armored power and control cables (ISI Marked) along with supplying & fixing of necessary

सत्यापित/CONTROLLED

channel/conduit, GI cable trays, supports, lugs, thimble and other accessories etc. as required.

10. DC Distribution Board and AC Distribution Panel Board: IP65, free standing, metal cladded, having copper bus bar, having required protection and control gears, connection-interconnection, etc. as required.
11. Any detailed clarification regarding Solar PV item, follow item no: MDSR 17.1.

डेटा वर्गीकरण : नियंत्रित/CONTROLLED