

## RFx

Gen-Open-SSTE

### Information

RFx number: 5002003891  
Version: 1

### RFx rules

Bidding Procedure : Public RFx  
Time zone : INDIA  
Package Specification No : NR2/NT/W-MISC/DOM/J01/24/12964  
Bid Submission Deadline : 02.10.2024 11:00:00

EMD Amount : 1,547,000.00 INR  
EMD Submission Deadline : 04.10.2024 11:00:00

RFx Default Currency : INR  
Opening date of technical Bid : 04.10.2024 11:30:00

#### Attachments:

VOLUME-I.ZIP  
VOLUME-II PART 1  
VOLUME-II PART 3.ZIP  
VOLUME-II PART 4.ZIP  
VOLUME-II PART 2.ZIP  
VOLUME -II PART 6.ZIP  
VOLUME-II PART 5.ZIP  
VOLUME-III.ZIP  
VOLUME-II PART 7.ZIP  
Digital Signature

### RFx details: Powergrid invites tenders for the items below

S.No	Material/Services	Short Description	Quantity/Unit	POWERGRID HSN/SAC	POWERGRID HSN/SAC Rate
------	-------------------	-------------------	---------------	-------------------	------------------------

**Rfx**

Gen-Open-SSTE

**Information**

Rfx number: 5002003891

Version: 1

				<b>Code</b>	<b>(%)</b>
1	Material	MS STEEL(GRADE C-IS 2062:2011)-NOR TOWER	209.664 MT	73082011	18.00
2	Material	MS STEEL(GRADE C-IS 2062:2011)TOWER STUB	7.181 MT	73082011	18.00
3	Material	HEXAGONAL BOLT & NUTS	7.615 MT	73181500	18.00
4	Material	BOLTS & NUTS FOR STUBS	0.170 MT	73181500	18.00
5	Material	ACSR MOOSE CONDUCTOR (KM)	24.596 KM	85041010	18.00
6	Material	COUNTERPOISE EARTHING (120M)	5.000 EA	73082011	18.00
7	Material	DANGER PLATE-400KV	5.000 EA	73082011	18.00
8	Material	NUMBER PLATE-400KV	5.000 EA	73082011	18.00
9	Material	PHASE PLATE (SET OF 3)	10.000 SET	73082011	18.00
10	Material	CIRCUIT PLATE (SET OF TWO)	5.000 SET	73082011	18.00
11	Material	ANTI-CLIMBING DEVICES-BARBED WIRE	5.000 SET	73082011	18.00
12	Outline	Erection Works	1 AU		0.00
12.AA	Service	CHECK SURVEY	1.975 KM	998344	18.00
12.AB	Service	EXCAVATION : DRY SOIL	594.339 M3	995433	18.00
12.AC	Service	EXCAVATION: DRY FISSURED ROCK	792.452 M3	995433	18.00
12.AD	Service	EXCAVATION: HARD ROCK	198.113 M3	995433	18.00
12.AE	Service	EXCAVATION: WET FISSURED ROCK	396.226 M3	995433	18.00
12.AF	Service	CONCRETING (1:1.5:3)	341.983 M3	995454	18.00
12.AG	Service	LEAN CONCRETE (1:3:6)	36.276 M3	995454	18.00
12.AH	Service	REINFORCEMENT STEEL	25.814 MT	995454	18.00
12.AJ	Service	STUB-NORMAL TOWERS USING TEMPLATE	7.351 MT	995455	18.00
12.AK	Service	NORMAL TOWER ERECTION	217.279 MT	995455	18.00
12.AL	Service	BENCHING:EXCEPT FISSURED/HARD ROCK/SANDY	286.759 M3	995432	18.00
12.AM	Service	BENCHING: FISSURED ROCK	477.932 M3	995432	18.00
12.AN	Service	BENCHING: HARD ROCK	191.173 M3	995432	18.00
12.AP	Service	TWR FOOTING PROT-RUBBLE STONE	1,964.136 M3	995456	18.00

For details of tender specification and other terms & conditions refer to the Bidding documents available at Technical Rfx tab

**Rfx**

Gen-Open-SSTE

**Information**

Rfx number: 5002003891

Version: 1

<b>12.AQ</b>	Service	TWR FOOTING PROT-M15 CONCRETE FOR COVER	10.617 M3	995456	18.00
<b>12.AR</b>	Service	TWR FOOTING PROT-BACKFILLING/GAP LEVEL	413.000 M3	995456	18.00
<b>12.AS</b>	Service	TOWER EARTHING-COUNTERPOISE 120M	5.000 EA	995468	18.00
<b>12.AT</b>	Service	DANGER PLATE INSTALLATION	5.000 EA	995444	18.00
<b>12.AU</b>	Service	NUMBER PLATE INSTALLATION	5.000 EA	995444	18.00
<b>12.AV</b>	Service	PHASE PLATE (SET OF 3) INSTALLATION	10.000 SET	995444	18.00
<b>12.AW</b>	Service	ANTI-CLIMBING DEVICES INSTALLATION	5.000 EA	995444	18.00
<b>12.AX</b>	Service	CIRCUIT PLATE (SET OF 2) INSTALLATION	5.000 SET	995444	18.00
<b>12.AY</b>	Service	STRINGING-400KV AC D/C TWIN CONDUCTOR	1.975 KM	995468	18.00
<b>12.AZ</b>	Service	SERVICE:OH 24 F JOINT BOX	2.000 EA	998716	18.00
<b>12.BA</b>	Service	DESTRINGING-400KV D/C LINE	0.210 KM	995468	18.00
<b>12.BB</b>	Service	DISMANTLING-TOWER	46.009 MT	995431	18.00

For details of tender specification and other terms & conditions refer to the Bidding documents available at Technical Rfx tab