

RFX

Gen-Limited-SSTE

Information

RFX number: 5006006217
Version: 1

RFX rules

Bidding Procedure : Restricted RFX
Time zone : INDIA
Package Specification No : ER2/NT/W-CIVIL/DOM/E00/25/08751
Bid Submission Deadline : 25.07.2025 11:00:00

EMD Amount : 43,000.00 INR
EMD Submission Deadline : 25.07.2025 11:00:00

RFX Default Currency : INR
Opening date of technical Bid : 25.07.2025 11:30:00

Attachments:
BID DOCS
Digital Signature

RFX details: Powergrid invites tenders for the items below

S.No	Material/Services	Short Description	Quantity/Unit	POWERGRID HSN/SAC Code	POWERGRID HSN/SAC Rate (%)
1	Outline	Brick Drain for Rainwater Harvesting	1 AU		0.00
1.AA	Service	2.6.1 EXCAVATION IN ALL SOILS D>30CM	118.574 M3	995433	18.00
1.AB	Service	2.7.1 EXCAVATION D>30CM ORDINARY ROCK	29.644 M3	995433	18.00
1.AC	Service	2.25M FILLING AVAILABLE EARTH	48.421 M3	995414	18.00
1.AD	Service	4.1.8 CC 1:4:8 <PL COARSE SAND&CA-40MM	11.772 M3	995454	18.00

For details of tender specification and other terms & conditions refer to the Bidding documents available at Technical Rfx tab

Rfx

Gen-Limited-SSTE

Information

Rfx number: 5006006217

Version: 1

1.AE	Service	4.1.3 CC 1:2:4 UPTO PLINTH LVL 20MM AGGR	0.273 M3	995454	18.00
1.AF	Service	5.9.1 FORM WORK FOR BASES OF COLUMNS	26.452 M2	995457	18.00
1.AG	Service	6.1.1 BW CD7.5 NM BRICKS <PLINTH CM1:4	25.903 M3	995456	18.00
1.AH	Service	13.1.2 12MM CEM PLASTER CM1:6(FINE SAND)	146.348 M2	995472	18.00
1.AJ	Service	13.18 NEAT CEMENT PUNNING	73.174 M2	995472	18.00
1.AK	Service	12.41.2 RIGID PVC RAIN WATER PIPES 110MM	5.000 M	995453	18.00
2	Outline	Recharge Well for Rainwater Harvesting	1 AU		0.00
2.AA	Service	2.6.1 EXCAVATION IN ALL SOILS D>30CM	190.759 M3	995433	18.00
2.AB	Service	2.7.1 EXCAVATION D>30CM ORDINARY ROCK	47.690 M3	995433	18.00
2.AC	Service	2.25M FILLING AVAILABLE EARTH	115.328 M3	995414	18.00
2.AD	Service	4.1.8 CC 1:4:8 <PL COARSE SAND&CA-40MM	31.320 M3	995454	18.00
2.AE	Service	5.1.2 RCC 1:1.5:3-ALL WORK UP TO PLINTH	52.776 M3	995454	18.00
2.AF	Service	13.18 NEAT CEMENT PUNNING	129.600 M2	995472	18.00
2.AG	Service	4.1.3 CC 1:2:4 UPTO PLINTH LVL 20MM AGGR	0.864 M3	995454	18.00
2.AH	Service	5.22.6 REINFORCEMENT STEEL-TMT BARS (MT)	3,648.330 MT	995454	18.00
2.AJ	Service	5.9.1 FORM WORK FOR BASES OF COLUMNS	18.720 M2	995457	18.00
2.AK	Service	5.9.2 FORM WORK FOR WALLS	259.200 M2	995457	18.00
2.AL	Service	10.2M STRUCTURAL STEEL WORK	688.680 KG	995414	18.00
2.AM	Service	13.61.1 SYNTHETIC ENAMEL PAINT-NEW WORK	33.490 M2	995473	18.00
2.AN	Service	24.9 PC RCC PERFORATED DRAIN COVERS	28.800 EA	995458	18.00
2.AP	Service	23.1.1.1 B/D BORE WELL-300MM	50.000 M	995458	18.00

For details of tender specification and other terms & conditions refer to the Bidding documents available at Technical Rfx tab

Rfx

Gen-Limited-SSTE

Information

Rfx number: 5006006217

Version: 1

		DIA			
2.AQ	Service	P&F Center Guide Set 150mm Dia	2.000 SET	995429	18.00
2.AR	Service	23.4.2S/A/L/FIX INVER POSITION BORE WELL	50.000 M	995458	18.00
2.AS	Service	24.14.2 MS CLAMP TOP OF TUBE WELL 150MM	2.000 EA	995458	18.00
2.AT	Service	23.5 S/F,SPREADING BOULDERS 5CM TO 20CM	16.556 M3	995458	18.00
2.AU	Service	23.6 S/F AND SPREADING GRAVEL 5-20MM	14.427 M3	995458	18.00
2.AV	Service	23.8 GRAVEL PACK TUBEWELL CONSTRUCTION	4.420 M3	995428	18.00
2.AW	Service	14.92 EXTRA COVERING TOP OF MEMBRANE	2.830 M2	995453	18.00
2.AX	Service	23.15.2 P/F BAIL PLUG/ BOTTOM PLUG	2.000 EA	995458	18.00
3	Outline	Storage Tank for Rainwater Harvesting	1 AU		0.00
3.AA	Service	2.6.1 EXCAVATION IN ALL SOILS D>30CM	547.978 M3	995433	18.00
3.AB	Service	2.7.1 EXCAVATION D>30CM ORDINARY ROCK	136.995 M3	995433	18.00
3.AC	Service	2.25 FILLING AVAILABLE EXCAVATED EARTH	154.495 M3	995433	18.00
3.AD	Service	4.1.8 CC 1:4:8 <PL COARSE SAND&CA-40MM	2.660 M3	995454	18.00
3.AE	Service	4.1.3 CC 1:2:4 UPTO PLINTH LVL 20MM AGGR	0.805 M3	995454	18.00
3.AF	Service	5.9.1 FORM WORK FOR BASES OF COLUMNS	14.000 M2	995457	18.00
3.AG	Service	6.1.1 BW CD7.5 NM BRICKS <PLINTH CM1:4	17.710 M3	995456	18.00
3.AH	Service	13.1.2 12MM CEM PLASTER CM1:6(FINE SAND)	170.100 M2	995472	18.00
3.AJ	Service	13.18 NEAT CEMENT PUNNING	93.100 M2	995472	18.00
3.AK	Service	23.1.1.1 B/D BORE WELL-300MM DIA	25.000 M	995458	18.00

For details of tender specification and other terms & conditions refer to the Bidding documents available at Technical Rfx tab

Rfx

Gen-Limited-SSTE

Information

Rfx number: 5006006217

Version: 1

3.AL	Service	P&F Center Guide Set 150mm Dia	1.000 SET	995429	18.00
3.AM	Service	23.4.2S/A/L/FIX INVER POSITION BORE WELL	25.000 M	995458	18.00
3.AN	Service	24.14.2 MS CLAMP TOP OF TUBE WELL 150MM	1.000 EA	995458	18.00
3.AP	Service	23.8 GRAVEL PACK TUBEWELL CONSTRUCTION	2.210 M3	995428	18.00
3.AQ	Service	14.92 EXTRA COVERING TOP OF MEMBRANE	0.590 M2	995453	18.00
3.AR	Service	2.31CLEAR JUNGLE UPROOT VEGETATION GRASS	600.000 M2	995433	18.00
3.AS	Service	23.15.2 P/F BAIL PLUG/ BOTTOM PLUG	1.000 EA	995458	18.00

For details of tender specification and other terms & conditions refer to the Bidding documents available at Technical Rfx tab