

## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 1 of 33

| S. No. | Description of Activity          | Tests/Checks to be done   | Ref. documents                                                                                                                                                                                                 | Existing Provisions      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                                                                                                                                                                                                             |                                  |
|--------|----------------------------------|---------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------|
|        |                                  |                           |                                                                                                                                                                                                                | Check/Testing            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Counter Check/Test by POWERGRID                                                                                                                                                                                             | Accepting authority in POWERGRID |
|        |                                  |                           |                                                                                                                                                                                                                | Agency                   | Extent                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                                                                                                             |                                  |
| 1.     | Civil Works                      |                           |                                                                                                                                                                                                                |                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                                                                                                                                                                                                             |                                  |
|        | <b>Materials</b><br><br>1.Cement | Brand approval            | Cement of approved brands according to the COV in POWERGRID web site may be procured through Manufacturer/Auth orized dealers having proper traceability. Refer COV in POWERGRID website for list of producers | Contractor               | As proposed by Contractor                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Any new brand cement proposed by Contractor shall be assessed by RHQ-FQA and approved by Regional Head with BIS License, validity. After approval, details shall be forwarded to CC FQA for uploading in COV                | Site In-charge                   |
|        |                                  | Physical & Chemical tests | As per document at Annexure-I of this FQP                                                                                                                                                                      | Contractor to submit MTC | (i) No physical testing is required in case of cement procured directly from the main producer/manufacture and if cement (in good condition without setting) is used within three (3) months from the manufacturing date based on MTC. MTC shall be reviewed<br><br>(ii) Testing (Physical & Chemical) shall be done in case storage of cement is more than three (3) months.<br><br>Note: In case small works having contract value not more than Rs 15 Lakhs, no testing is required in case cement procured directly from the main producer/manufacture or authorised /notified distributor/dealer of the Main producer and if cement (in good condition without setting) is used within three (3) months from the manufacturing date based on MTC. MTC shall be reviewed. | 100% review of lab test results.<br>Test results shall be sent by the Lab. by E-mail directly to POWERGRID. Further, a hard copy of test certificate shall also be sent by the Lab directly to POWERGRID by postal Address. | Site Engineer                    |



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 2 of 33

| S. No. | Description of Activity            | Tests/Checks to be done             | Ref. documents                                                                                                                                                                                                                                                                          | Existing Provisions      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                  |                                  |
|--------|------------------------------------|-------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------|
|        |                                    |                                     |                                                                                                                                                                                                                                                                                         | Check/Testing            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Counter Check/Test by POWERGRID                                                                                                                                                                                                                                                                                                                                                                                  | Accepting authority in POWERGRID |
|        |                                    |                                     |                                                                                                                                                                                                                                                                                         | Agency                   | Extent                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                  |                                  |
|        | 2.a)<br><b>Reinforcement Steel</b> | Brand approval                      | Reinforcement Steel of approved brands according to COV in POWERGRID website may be procured through Manufacturer/Authorized dealers having proper traceability. Refer COV in POWERGRID website for list of producers of reinforcement steel and validity of BIS license to be ensured. | Contractor               | As proposed by contractor.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 100% review of MTC and 100% physical verification of embossing of manufacturer's trademark at site and photographs of the same with record                                                                                                                                                                                                                                                                       | Site In-charge                   |
|        |                                    | Physical and Chemical analysis test | As per Annexure-2 of this FQP                                                                                                                                                                                                                                                           | Contractor to submit MTC | <p>i) Steel suppliers shall be approved by POWERGRID at Corporate level as per the existing practice.</p> <p>ii) No testing is required for steel procured directly from POWERGRID pre-approved producers as per COV under CAT-I or their notified authorized dealers with full traceability (only MTC shall be reviewed) as no failure in physical and chemical testing observed in last decade by POWERGRID. (CAT-I: Approved Vendor List in COV)</p> <p>iii) For other vendors under CAT-II or their notified dealers / new vendors, frequency testing of Reinforcement steel is to be done at regular intervals as per the existing SFQP. Based on the supply, experience and</p> | <p>100% review of MTC.</p> <p>1) Review of Lab test results. Test results shall be sent by the Lab. by E-mail directly to POWERGRID; further, a hard copy of test certificate shall also be sent by the Lab. directly to POWERGRID by postal Address:-</p> <p>CAT II- Unit weight of three samples to be witnessed. ##</p>  | Site Engineer                    |



# STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 3 of 33

| S. No. | Description of Activity                                                                     | Tests/Checks to be done                              | Ref. documents                             | Existing Provisions |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                          |                                  |
|--------|---------------------------------------------------------------------------------------------|------------------------------------------------------|--------------------------------------------|---------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------|----------------------------------|
|        |                                                                                             |                                                      |                                            | Check/Testing       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Counter Check/Test by POWERGRID                          | Accepting authority in POWERGRID |
|        |                                                                                             |                                                      |                                            | Agency              | Extent                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                          |                                  |
|        |                                                                                             |                                                      |                                            |                     | <p>performance upto one-year, further decision on exemption of testing for these vendors shall be taken by FQA dept. (CAT-II: New Vendors listed in COV/ New Vendors)</p> <p>CAT-II - One sample* / 100MT / Manufacturer shall be jointly sealed by POWERGRID and tested at POWERGRID approved Lab.</p> <p>* <u>Note:</u> All sizes of 10mm and above shall be taken for testing in every 100MT.</p> <p># # Three samples of each size of Reinforcement steel (all sizes of 10mm &amp; above) out of 100MT steel Lot need to be physically weight at site in presence of POWERGRID to ascertain their acceptance as per technical specification. The weighted samples at site may be kept under custody for three months for further examination by any auditing authority (if required).</p> <p>If the total quantity requirement is less than 5 MT. MTC shall be reviewed; no testing is required</p> |                                                          |                                  |
|        | 2.b) Steel Jointing Coupler                                                                 |                                                      | IS 16172:2023                              | Contractor          | <p>Use of Couplers for jointing reinforcement steel:</p> <p>In addition to present TS Provisions, Reinforcement couplers for mechanical splices of bars in concrete is incorporated as per IS 16172:2023 as an alternative to the present practices</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 100% (Steel Jointing Coupler shall comply IS 16172:2023) | Site Engineer                    |
|        | 2. b) Structural steel. For roof truss, door & window frames, boundary wall, gates, grills, | Brand to be proposed by Contractor<br><br>1. Visual& | POWERGRID Specification & approved drawing | Contractor          | As proposed by contractor                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | To verify the documents                                  | Site In charge                   |



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 4 of 33

| S. No. | Description of Activity                  | Tests/Checks to be done                                                                                          | Ref. documents                                                                                                                                                                                                                                                       | Existing Provisions |                   |                                 |                                  |
|--------|------------------------------------------|------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|-------------------|---------------------------------|----------------------------------|
|        |                                          |                                                                                                                  |                                                                                                                                                                                                                                                                      | Check/Testing       |                   | Counter Check/Test by POWERGRID | Accepting authority in POWERGRID |
|        |                                          |                                                                                                                  |                                                                                                                                                                                                                                                                      | Agency              | Extent            |                                 |                                  |
|        | railings gratings & rolling shutter etc. | 1. Dimensional check for damages, rusting & pitting, welding, primer coating, painting/galvanizing as applicable |                                                                                                                                                                                                                                                                      |                     | 100%              | random                          | Site Engineer                    |
|        |                                          | 2. Physical properties<br>a) Structural Steel (including tubular pipes)                                          | Unit weight for each section/each brand to be carried out in presence of POWERGRID to ascertain their acceptance as per technical specification/IS.<br><br>The weighted samples at site may be kept under custody till completion of tenure of contract with records | Contractor          | Review of all MTC | 100% review of MTC results      | Site In charge                   |




## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 5 of 33

| S. No. | Description of Activity     | Tests/Checks to be done                                                  | Ref. documents                                                 | Existing Provisions                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                     |
|--------|-----------------------------|--------------------------------------------------------------------------|----------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------|
|        |                             |                                                                          |                                                                | Check/Testing                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Counter Check/Test by POWERGRID                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Accepting authority in POWERGRID                                                                                                                    |
|        |                             |                                                                          |                                                                | Agency                                                                                                                                             | Extent                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                     |
|        | 3.Coarse Aggregates         | Source approval (if approved source is not available in the vicinity)    | As per Annexure-3 of this SFQP                                 | Contractor                                                                                                                                         | Proposed by the Contractor, indicating the location of the quarry and based on the test results of Joint samples tested in POWERGRID approved Lab.                                                                                                                                                                                                                                                                                                                           | 100% review of test results                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Site In-charge<br><br>Once approved, the particular quarry shall be used for all the running packages.                                              |
|        | 4.Fine aggregate            | 1. Source approval (if approved source is not available in the vicinity) | As per Annexure-4 of this SFQP                                 | Contractor                                                                                                                                         | Proposed by the Contractor, indicating the location of the quarry/River Ghat based on the results of joint samples tested in POWERGRID approved lab.                                                                                                                                                                                                                                                                                                                         | 100% review of test results                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Site In-charge<br><br>Once approved, the particular quarry/River Ghat shall be used for all the running packages.                                   |
|        | 5. Water                    | 1. Cleanliness                                                           | POWERGRID Specification (Water shall be fresh and clean)       | Contractor                                                                                                                                         | 100% visual check at Field                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Verification at random                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Site Engineer                                                                                                                                       |
|        |                             | 2. Ph Value                                                              | - do -                                                         | Contractor                                                                                                                                         | One sample per source with calibrated Ph meter at site                                                                                                                                                                                                                                                                                                                                                                                                                       | 100% review of the field test results<br>Ph not less than 6                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Site Engineer                                                                                                                                       |
| 2.0    | Concrete Strength (For RCC) | Cubes Compressive Strength                                               | As per POWERGRID Specification. As per Annexure-5 of this SFQP | Contractor Casting . of cubes at site. Cubes to be tested for 28 days strength at POWERGR ID In-house Lab/At site (if testing machine installed by | <b>Nominal Mix</b><br>One sample of 3 cubes for every 20 cum or part thereof for each day of concreting and 28 days compressive-strength shall be tested.<br><b>Design Mix</b><br>Sampling for concrete strength should be one set of 3 nos. of cubes for every 20 cum or part thereof for each day of concreting and 28 days compressive strength shall be tested.<br><br>However, in case of concrete supplied by RMC, one set of 3 nos. of cubes for every 50 cum or part | Normally testing shall be carried out at the POWERGRID in-house cube testing facility. Alternatively, samples shall be tested at cube testing facility installed by contractor at POWERGRID premises, in the witness of POWERGRID. Lastly, POWERGRID approved Labs, in this case, test results shall be sent by the Lab, by E-mail directly to POWERGRID; further, a hard copy of Test Certificate shall also be sent by the Lab directly to POWERGRID by Postal Address.<br><b>NOTE: The efforts shall be made to carry out 100% cube testing in the in-house cube</b> | Site Engineer.<br><br>Testing to be witnessed by POWERGRID<br> |

# STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 6 of 33

| S. No. | Description of Activity                                        | Tests/Checks to be done                         | Ref. documents                | Existing Provisions                                                                                                                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                |
|--------|----------------------------------------------------------------|-------------------------------------------------|-------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------|
|        |                                                                |                                                 |                               | Check/Testing                                                                                                                                    | Counter Check/Test by POWERGRID                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Accepting authority in POWERGRID               |
|        |                                                                |                                                 |                               | Agency                                                                                                                                           | Extent                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                                |
|        |                                                                |                                                 |                               | contractor is duly calibrated by NABL Lab.)/ POWERGR ID approved Lab Cubes at 100% location are to be taken in presence of POWERGR ID officials. | thereof for each day of concreting and 28 days compressive strength shall be tested.<br><br>Concrete Cube collection & testing in case of RMC:<br><br>Ready Mix Concrete (RMC) may be allowed and testing/acceptance documentation to be maintained shall be as per as per IS: 4926:2003, Reaffirmed 2022. Concrete cube sampling should be done at site. However, in case cube samples cannot be taken at site, taking of cube samples at RMC is acceptable.<br><br>Concrete composition and batch record for each and every lot shall be maintained as per IS: 4926:2003, Reaffirmed 2022. The raw material in the RMC bins must be from approved sources/ brands make Concrete Cube collection & testing in case of RMC: | testing facility.                              |
|        | Use of admixtures in concreting both in nominal and design mix | To achieve workability as per site requirement. | IS 9103:1999, Reaffirmed 2018 | Contractor                                                                                                                                       | Use as per IS 9103:1999, Reaffirmed 2018 to achieve workability.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 20 % check at random<br><br>Engineer-in-Charge |
|        | C) Membrane Curing                                             |                                                 | IS 456:2000, Reaffirmed 2021  | Contractor                                                                                                                                       | In addition to the moist curing of cast concrete structures, membrane curing is also introduced as per IS 456:2000, Reaffirmed 2021/ Manufacturer's catalogue.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 100%<br><br>Engineer-in-Charge                 |




## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 7 of 33

| S. No. | Description of Activity                                | Tests/Checks to be done                                                                                                                                 | Ref. documents                                                                   | Existing Provisions                                                           |                                                                                                           |                                 |                                  |
|--------|--------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------|-------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------|---------------------------------|----------------------------------|
|        |                                                        |                                                                                                                                                         |                                                                                  | Check/Testing                                                                 |                                                                                                           | Counter Check/Test by POWERGRID | Accepting authority in POWERGRID |
|        |                                                        |                                                                                                                                                         |                                                                                  | Agency                                                                        | Extent                                                                                                    |                                 |                                  |
|        | D) Use of PVC Block in place of Concrete Cover Blocks: | To be Procured as per IS                                                                                                                                | IS 456:2000, Reaffirmed 2021                                                     | Contractor                                                                    | 100%                                                                                                      | 100%                            | Engineer-in-Charge               |
| 3.     | Brick Masonry                                          |                                                                                                                                                         |                                                                                  |                                                                               |                                                                                                           |                                 |                                  |
|        | a) Clay Bricks<br>b) Fly Ash Bricks                    | Physical tests<br>1. Dimensional Tolerance (For a particular work where less than 5000 nos of bricks are to be used, only visual checks are to be done) | POWERGRID Spec/enclosed at Annex-6                                               | Contractor (samples to be taken jointly and tested in POWERGRID accepted lab) | Enclosed Annex-6                                                                                          | 100% review of test results     | Site Engineer                    |
|        |                                                        | 2. Compressive Strength                                                                                                                                 | POWERGRID Spec/enclosed at Annex-6                                               | --do--                                                                        | --do--                                                                                                    | --do--                          | Site Engineer                    |
|        |                                                        | 3. Water Absorption                                                                                                                                     | POWERGRID Spec/enclosed at Annex-6                                               | --do--                                                                        | --do--                                                                                                    | --do--                          | Site Engineer                    |
|        |                                                        | 4. Efflorescence                                                                                                                                        | POWERGRID Spec/enclosed at Annex-6                                               | --do--                                                                        | --do--                                                                                                    | --do--                          | Site Engineer                    |
| 4.     | Stone for Masonry                                      |                                                                                                                                                         |                                                                                  |                                                                               |                                                                                                           |                                 |                                  |
|        | Stone                                                  | 1. Compressive Strength (if approved source is                                                                                                          | IS: 1121:2023 (Part-1) & CPWD Specification clause 7.1. Stone with round surface | By Contractor                                                                 | One sample per source shall be tested in POWERGRID approved Lab, if the volume of stone masonry is >25cum | 100% review of test results     | Site Engineer                    |




## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 8 of 33

| S. No. | Description of Activity                                                                                      | Tests/Checks to be done                                                   | Ref. documents                                                                                            | Existing Provisions |                                                                                                             |                                                                                                                                                                                                                                   |                                  |
|--------|--------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------|---------------------|-------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------|
|        |                                                                                                              |                                                                           |                                                                                                           | Check/Testing       |                                                                                                             | Counter Check/Test by POWERGRID                                                                                                                                                                                                   | Accepting authority in POWERGRID |
|        |                                                                                                              |                                                                           |                                                                                                           | Agency              | Extent                                                                                                      |                                                                                                                                                                                                                                   |                                  |
|        |                                                                                                              | not available in the vicinity)                                            | shall not be used                                                                                         |                     |                                                                                                             |                                                                                                                                                                                                                                   |                                  |
|        |                                                                                                              | 2. Water Absorption (if approved source is not available in the vicinity) | IS:1124-1974, Reaffirmed 2022 & CPWD Specification clause 7.1. Stone with round surface shall not be used | By Contractor       | One sample per source shall be tested in POWERGRID approved Lab, if the volume of stone masonry is > 25 cum | 100% review of test results                                                                                                                                                                                                       | Site Engineer                    |
| 5.     | Tiles for Flooring & Walls<br><br>1. Glazed Tiles<br>2. Vitrified Tiles                                      |                                                                           | IS: 15622:2017, Reaffirmed 2022 & POWERGRID Specification                                                 |                     |                                                                                                             | In case of vitrified/glazed tiles conforming to IS 15622:2017, Reaffirmed 2022, testing provision is deleted from SFQP and vitrified/glazed tiles of POWERGRID approved make may be accepted on the basis of documents/catalogues | Site In charge                   |
| 6.     | Finishing Materials of Building<br><br>Type/quality/class of finishing building material (of approved brand) | Physical verification of different items as per Spec                      | POWERGRID Specifications                                                                                  | Contractor          | 100%                                                                                                        | 100%                                                                                                                                                                                                                              | Site In charge                   |
| 7.     | Timber<br>1. Timber for Door & Window Frame                                                                  | Moisture content                                                          | IS: 287:1993, Reaffirmed 2022 & CPWD Specification                                                        | By Contractor       | 100%<br>If total quantity of timber is > 0.5 cum                                                            | 100% review of MTC results, if MTC is not available 1 sample to be tested at POWERGRID approved Lab                                                                                                                               | Site In charge                   |
|        | 2. Flush Door Shutters (factory made)                                                                        | 1. End Immersion Test<br><br>1. Knife Test<br>2. Glue Adhesion            | POWERGRID Specification                                                                                   | By Contractor       | 100%<br>If total quantity of shutters is > 20 nos.                                                          | 100% review of MTC results, if MTC is not available 1 sample to be tested at POWERGRID approved Lab                                                                                                                               | Site In charge                   |



# STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 9 of 33

| S. No. | Description of Activity                                         | Tests/Checks to be done                                     | Ref. documents                                                                                   | Existing Provisions      |                                                                                                                                                    |                                                                                                          |                                                           |
|--------|-----------------------------------------------------------------|-------------------------------------------------------------|--------------------------------------------------------------------------------------------------|--------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|-----------------------------------------------------------|
|        |                                                                 |                                                             |                                                                                                  | Check/Testing            |                                                                                                                                                    | Counter Check/Test by POWERGRID                                                                          | Accepting authority in POWERGRID                          |
|        |                                                                 |                                                             |                                                                                                  | Agency                   | Extent                                                                                                                                             |                                                                                                          |                                                           |
| 8.     | Aluminum Door & Window sections                                 | Physical & Chemical Properties                              | IS: 733:1983, reaffirmed 2022 & IS:1285:2023 Specifications enclosed at Annexure-9               | Contractor to submit MTC | Review of all MTCs                                                                                                                                 | 100% review of test results                                                                              | Site Engineer                                             |
|        | 1.Physical & Chemical Properties<br><br>2.Anodic/Powder coating | Thickness of Coating                                        | IS: 5523:1983, Reaffirmed 2021, POWERGRID specification, approved drawings & CPWD specifications | By Contractor            | 100%<br>If total quantity is >200Kgs                                                                                                               | Review of MTC results/ If MTC is not furnished one sample per lot to be tested at POWERGRID approved Lab | Site Engineer                                             |
| 9.     | G.S Barbed Wire (Concertina Fencing Coil)                       | 1. Visual Check                                             | IS: 278:2009, POWERGRID specification & CPWD specification. Refer Annexure-7 of this FQP         | Contractor               | 100%                                                                                                                                               | 100% review of MTC results, if MTC is not available 1 sample to be tested at POWERGRID approved Lab      | Site Engineer                                             |
|        |                                                                 | 2. Dimensional, Weight & Size                               |                                                                                                  | Contractor               | 100%                                                                                                                                               |                                                                                                          |                                                           |
|        |                                                                 | 3.Tensile Test, Zinc coating test and ductility test        | IS: 278, POWERGRID specification & CPWD specification. Refer Annexure-7 of this FQP              | Contractor               | 100%                                                                                                                                               | 100% review of MTC results, if MTC is not available 1 sample to be tested at POWERGRID approved Lab      | Site Engineer                                             |
| 10.    | Road (WBM/WMM layers)                                           | Source approval (if approved source is not available in the | As per document at Annexure-8 of this SFQP                                                       | Contractor               | Proposed by the contractor, indicating the location of the quarry and based on the test results of joint samples tested in POWERGRID accepted lab. | 100% review of test results                                                                              | Site In charge<br><br>Once approved the particular quarry |



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 10 of 33

| S. No. | Description of Activity      | Tests/Checks to be done                                                                  | Ref. documents                             | Existing Provisions |                                                                                                                                                   |                                            |
|--------|------------------------------|------------------------------------------------------------------------------------------|--------------------------------------------|---------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------|
|        |                              |                                                                                          |                                            | Check/Testing       |                                                                                                                                                   | Counter Check/Test by POWERGRID            |
|        |                              |                                                                                          |                                            | Agency              | Extent                                                                                                                                            | Accepting authority in POWERGRID           |
|        | Material                     | vicinity)                                                                                |                                            |                     |                                                                                                                                                   |                                            |
|        | A) Coarse Aggregate          |                                                                                          |                                            |                     |                                                                                                                                                   | shall be used for all the running packages |
|        | B) Stone Screening           | 1.Source approval (if approved source is not available in the vicinity)                  | As per document at Annexure-8 of this SFQP | Contractor          | Proposed by the contractor, indicating the location of the quarry and based on the test results of joint samples tested in POWERGRID accepted lab | 100% review of test results                |
|        | C) Binding Material          | Source approval (Plasticity Index) (if approved source is not available in the vicinity) | As per document at Annexure-8 of this SFQP | Contractor          | Proposed by the contractor, indicating the location of the quarry and based on the test results of joint samples tested in POWERGRID accepted lab | 100% review of lab test results            |
|        | D) Laying of sub base course | Physical check                                                                           | As per CPWD Spec Clause 17.7.2             | Contractor          | 100%                                                                                                                                              | Random                                     |
|        | E) Laying of base Course     | Physical check                                                                           | As per CPWD Spec Clause 17.8.1             | Contractor          | 100%                                                                                                                                              | Random                                     |



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 11 of 33

**Annexure-1(Sheet 01 of 03)**

### ACCEPTANCE CRITERIA AND PERMISSIBLE LIMITS FOR CEMENT

| ORDINARY PORTLAND CEMENT |                              |                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                          |                                                                                                                                                                                             |                                                                                |
|--------------------------|------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------|
| S. No.                   | Name of the test             | Ordinary Portland Cement 33 grade as per IS 269: 2015                                                                                                                                                                                     | Ordinary Portland Cement 43 grade as per IS 269: 2015                                                                                                                                                                                    | Ordinary Portland Cement 53 grade as per IS 269: 2015                                                                                                                                       | Remarks                                                                        |
| a)                       | Physical tests               |                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                          |                                                                                                                                                                                             | To be conducted in POWERGRID approved Lab                                      |
| (i)                      | Fineness                     | Specific surface area shall not be less than 225 sq.m. per Kg. or 2250 cm <sup>2</sup> per gm.                                                                                                                                            | Specific surface area shall not be less than 225 sq.m. per Kg or 2250 cm <sup>2</sup> per gm.                                                                                                                                            | Specific surface area shall not be less than 225 sq.m. per Kg or 2250 cm <sup>2</sup> per gm.                                                                                               | Blaine's air permeability method as per IS 4031 (Part-2):1999, Reaffirmed 2023 |
| (ii)                     | Compressive strength         | 72 ± 1 hour: Not less than 16 Mpa (16 N/mm <sup>2</sup> )<br><br>168 ± 2 hour: Not less than 22 Mpa (22 N/mm <sup>2</sup> )<br><br>672 ± 4 hour: Not less than 33 Mpa (33 N/mm <sup>2</sup> ), Not more than 48Mpa (48N/mm <sup>2</sup> ) | 72 ± 1 hour: Not less than 23 Mpa (23 N/mm <sup>2</sup> )<br><br>168 ± 2 hour: Not less than 33Mpa (33 N/mm <sup>2</sup> )<br><br>672 ± 4 hour: Not less than 43 Mpa (43 N/mm <sup>2</sup> ), Not more than 58Mpa (58N/mm <sup>2</sup> ) | 72 ± 1 hour: Not less than 27Mpa (27 N/mm <sup>2</sup> )<br><br>168 ± 1 hour: Not less than 37Mpa (37 N/mm <sup>2</sup> )<br><br>672 ± 1 hour: Not less than 53 Mpa (53 N/mm <sup>2</sup> ) | As per IS 4031 (Part-6): 1988, Reaffirmed 2024                                 |
| (iii)                    | Initial & Final setting time | Initial setting time: Not less than 30 minutes<br><br>Final setting time: Not more than 600 minutes                                                                                                                                       | Initial setting time: Not less than 30 minutes<br><br>Final setting time: Not more than 600 minutes                                                                                                                                      | Initial setting time: Not less than 30 minutes<br><br>Final setting time: Not more than 600 minutes                                                                                         | As per IS 4031 (Part-5): 1988 Reaffirmed 2024.<br><br>-do-                     |
| iv)                      | Soundness                    | Unaerated cement shall not have an expansion of more than 10mm when tested by Le Chatlier and 0.8% by Autoclave test.                                                                                                                     | Unaerated cement shall not have an expansion of more than 10mm when tested by Le Chatlier and 0.8% by Autoclave test                                                                                                                     | Unaerated cement shall not have an expansion of more than 10mm when tested by Le Chatlier and 0.8% by Autoclave test.                                                                       | Le Chatlier and Autoclave test as per IS 4031 (Part-3): 1988, Reaffirmed 2024. |




# STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 12 of 33  
Annexure-1(Sheet 02 of 03)

| S. No. | Name of the test           | Ordinary Portland Cement 33 grade as per IS 269                                                                       | Ordinary Portland Cement 43 grade as per IS 269                                                                       | Ordinary Portland Cement 53 grade as per IS 269                                                                       | Remarks            |
|--------|----------------------------|-----------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|--------------------|
| b)     | Chemical composition tests |                                                                                                                       |                                                                                                                       |                                                                                                                       | Review of MTC only |
|        |                            | a) Ratio of percentage of lime to percentage of silica, alumina & iron oxide 0.66 to 1.02%                            | a) Ratio of percentage of lime to percentage of silica, alumina & iron oxide 0.66 to 1.02%                            | a) Ratio of percentage of lime to percentage of silica, alumina & iron oxide 0.80 to 1.02%                            |                    |
|        |                            | b) Ratio of percentage of alumina to that of iron oxide Minimum 0.66%                                                 | a) Ratio of percentage of alumina to that of iron oxide Minimum 0.66%                                                 | a) Ratio of percentage of alumina to that of iron oxide Minimum 0.66%                                                 |                    |
|        |                            | c) Insoluble residue, percentage by mass Max. 5.00%                                                                   | c) Insoluble residue, percentage by mass Max. 5.00%                                                                   | c) Insoluble residue, percentage by mass Max. 5.00%                                                                   |                    |
|        |                            | d) Magnesia percentage by mass Max. 6%                                                                                | d) Magnesia percentage by mass Max. 6%                                                                                | d) Magnesia percentage by mass Max. 6%                                                                                |                    |
|        |                            | e) Total Sulphur content calculated as sulphuric anhydride (SO <sub>3</sub> ), percentage by mass not more than 3.5%. | e) Total Sulphur content calculated as sulphuric anhydride (SO <sub>3</sub> ), percentage by mass not more than 3.5%. | e) Total sulphur content calculated as sulphuric anhydride (SO <sub>3</sub> ), percentage by mass not more than 3.5%. |                    |
|        |                            | f) Total loss on ignition shall not be more than 5 percent                                                            | f) Total loss on ignition shall not be more than 5 percent                                                            | f) Total loss on ignition shall not be more than 4 percent                                                            |                    |
|        |                            | g) Chloride content, percent by mass, max 0.1%                                                                        | g) Chloride content, percent by mass, max 0.1%                                                                        | g) Chloride content, percent by mass, max 0.1%                                                                        |                    |



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 13 of 33

### Annexure-1 (Sheet 03 of 03)

| S. No. | Name of the test                                                                                               |                                                                                                                                                                       |                                                                                                                                                                                                | Remarks            |
|--------|----------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|
| 2.     | PORTLAND POZZOLANA CEMENT AS PER IS 1489 (Part 1) To be conducted in POWERGRID approved Lab/Review of MTC only |                                                                                                                                                                       |                                                                                                                                                                                                |                    |
| a)     | Physical tests                                                                                                 | i) Fineness                                                                                                                                                           | Specific surface area shall not be less than 300 sq.m. per Kg. or 3000 Cm <sup>2</sup> per gm.                                                                                                 |                    |
|        |                                                                                                                | ii) Compressive strength                                                                                                                                              | a) 72 ± 1 hour: Not less than 16 Mpa (16 N/mm <sup>2</sup> )<br>b) 168 ± 2 hour: Not less than 22 Mpa (22 N/mm <sup>2</sup> )<br>c) 672 ± 4 hour: Not less than 33 Mpa (33 N/mm <sup>2</sup> ) |                    |
|        |                                                                                                                | iii) Initial & Final setting time                                                                                                                                     | Initial setting time: Not less than 30 minutes<br>Final setting time: Not more than 600 minutes                                                                                                |                    |
|        |                                                                                                                | iv) Soundness                                                                                                                                                         | Un aerated cement shall not have an expansion of more than 10mm Le chatlier test and 0.8% by Autoclave test as per IS 4031:1988, reaffirmed 2019 (Part-3)                                      |                    |
| b)     | Chemical composition tests                                                                                     |                                                                                                                                                                       |                                                                                                                                                                                                |                    |
|        |                                                                                                                | a) Magnesia percentage by mass Max. 6%                                                                                                                                |                                                                                                                                                                                                | Review of MTC only |
|        |                                                                                                                | b) Insoluble residue, percent by mass, (a) Maximum {x + 4 (100-x)/100} (b) Minimum 0.6x, where x is the declared % of fly ash in the given Portland pozzolana cement. |                                                                                                                                                                                                | -do-               |
|        |                                                                                                                | c) Total sulphur content calculated as sulphuric anhydride (SO <sub>3</sub> ), percentage by mass not more than 3.5                                                   |                                                                                                                                                                                                | -do-               |
|        |                                                                                                                | d) Total loss on ignition shall not be more than 5 percent                                                                                                            |                                                                                                                                                                                                |                    |
|        |                                                                                                                | e) Chloride content, percent by mass, max 0.1%                                                                                                                        |                                                                                                                                                                                                |                    |



**STANDARD FIELD QUALITY PLAN**

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 14 of 33

**ACCEPTANCE CRITERIA AND PERMISSIBLE LIMITS FOR REINFORCEMENT STEEL****Annexure-2****AS PER IS 1786:2018, Amendment No. - 4**

| S. No. | Name of the test                                                | Fe 500                                                            | Fe 500D                                                           | Fe 550                                                            | Fe 550D                                                           |
|--------|-----------------------------------------------------------------|-------------------------------------------------------------------|-------------------------------------------------------------------|-------------------------------------------------------------------|-------------------------------------------------------------------|
| i)     | <b>Chemical analysis test</b>                                   |                                                                   |                                                                   |                                                                   |                                                                   |
|        | Carbon                                                          | 0.30 Percent Maximum                                              | 0.25 Percent Maximum                                              | 0.30 Percent Maximum                                              | 0.25 Percent Maximum                                              |
|        | Sulphur                                                         | 0.055 Percent Maximum                                             | 0.040 Percent Maximum                                             | 0.055 Percent Maximum                                             | 0.040 Percent Maximum                                             |
|        | Phosphorus                                                      | 0.055 Percent Maximum                                             | 0.040 Percent Maximum                                             | 0.055 Percent Maximum                                             | 0.040 Percent Maximum                                             |
|        | Sulphur & Phosphorus                                            | 0.105 Percent Maximum                                             | 0.075 Percent Maximum                                             | 0.10 Percent Maximum                                              | 0.075 Percent Maximum                                             |
|        | Carbon Equivalent                                               | 0.42 percent Maximum                                              | 0.50 percent Maximum                                              | 0.50 percent Maximum                                              | 0.61 percent Maximum                                              |
| ii)    | <b>Physical tests</b>                                           |                                                                   |                                                                   |                                                                   |                                                                   |
|        | a) Tensile Strength/Yield stress ratio,                         | ≥1.08, but tensile strength not less than 545.0 N/mm <sup>2</sup> | ≥1.10, but tensile strength not less than 565.0 N/mm <sup>2</sup> | ≥1.06, but tensile strength not less than 585.0 N/mm <sup>2</sup> | ≥1.08, but tensile strength not less than 600.0 N/mm <sup>2</sup> |
|        | b) 0.2% of proof stress/Yield stress Minimum, N/mm <sup>2</sup> | 500                                                               | 500                                                               | 550                                                               | 550                                                               |
|        | c) Elongation percent, Minimum                                  | 12                                                                | 16                                                                | 10                                                                | 14.5                                                              |
|        | d) Total elongation at maximum force, percent, Minimum          | —                                                                 | 5                                                                 | 5                                                                 | 5                                                                 |
| iii)   | <b>Bend &amp; Rebend tests</b>                                  | Pass                                                              | Pass                                                              | Pass                                                              | Pass                                                              |



# STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 15 of 33  
Annexure-3

## ACCEPTANCE CRITERIA AND PERMISSIBLE LIMITS FOR COARSE AGGREGATES AS PER IS 383:2016

|    |                                                               |                                                                                                                                                |                                                         |           |           |           |           |                                                         |           |          |           |
|----|---------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------|-----------|-----------|-----------|-----------|---------------------------------------------------------|-----------|----------|-----------|
| 3. | Coarse Aggregates                                             |                                                                                                                                                |                                                         |           |           |           |           |                                                         |           |          |           |
| i) | Physical Tests                                                |                                                                                                                                                |                                                         |           |           |           |           |                                                         |           |          |           |
|    | a) Determination of particles size                            | a. IS Sieve Designation                                                                                                                        | %age passing for Single-Sized Aggregate of nominal size |           |           |           |           | Percentage Passing for graded Aggregate of nominal size |           |          |           |
|    |                                                               |                                                                                                                                                | 40 mm                                                   | 20 mm     | 16 mm     | 12.5 mm   | 10 mm     | 40 mm                                                   | 20 mm     | 16 mm    | 12.5 mm   |
|    |                                                               | 63 mm                                                                                                                                          | 100                                                     | -         | -         | -         | -         | -                                                       | -         | -        | -         |
|    |                                                               | 40 mm                                                                                                                                          | 85 to 100                                               | 100       | -         | -         | -         | 90 to 100                                               | 100       | -        | -         |
|    |                                                               | 20 mm                                                                                                                                          | 0 to 20                                                 | 85 to 100 | 100       | -         | -         | 30 to 70                                                | 90 to 100 | 100      | 100       |
|    |                                                               | 16 mm                                                                                                                                          | -                                                       | -         | 85 to 100 | 100       | -         | -                                                       | -         | 90-100   | -         |
|    |                                                               | 12.5 mm                                                                                                                                        | -                                                       | -         | -         | 85 to 100 | 100       | -                                                       | -         | -        | 90 to 100 |
|    |                                                               | 10 mm                                                                                                                                          | 0 to 5                                                  | 0 to 20   | 0 to 30   | 0 to 45   | 85 to 100 | 10 to 35                                                | 25 to 55  | 30 to 70 | 40 to 85  |
|    |                                                               | 4.75 mm                                                                                                                                        | -                                                       | 0 to 5    | 0 to 5    | 0 to 10   | 0 to 20   | 0 to 5                                                  | 0 to 10   | 0 to 10  | 0 to 10   |
|    |                                                               | 2.36 mm                                                                                                                                        | -                                                       | -         | -         | -         | 0 to 5    | -                                                       | -         | -        | -         |
|    | b. Combined Flakiness and Elongation index                    | Not to exceed 40%                                                                                                                              |                                                         |           |           |           |           |                                                         |           |          |           |
|    | c. Crushing Value                                             | Not to exceed 30%                                                                                                                              |                                                         |           |           |           |           |                                                         |           |          |           |
|    | d. Presence of deleterious material                           | Total presence of deleterious materials not to exceed 5% for uncrushed, 2% for crushed and manufactured coarse aggregates as per Annexure- 3A. |                                                         |           |           |           |           |                                                         |           |          |           |
|    | e. Hardness                                                   | Abrasion value not more than 50%, Impact value not more than 45%                                                                               |                                                         |           |           |           |           |                                                         |           |          |           |
|    | f. Soundness test (for concrete work subject to frost action) | Not to exceed 12% when tested with sodium sulphate and 18% when tested with magnesium sulphate                                                 |                                                         |           |           |           |           |                                                         |           |          |           |



**STANDARD FIELD QUALITY PLAN**

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 16 of 33  
**Annexure-3A**

| Deleterious Substance                                                                                                             | Percentage by Mass, Max |         |              |
|-----------------------------------------------------------------------------------------------------------------------------------|-------------------------|---------|--------------|
|                                                                                                                                   | Uncrushed               | Crushed | Manufactured |
| a) Coal and lignite                                                                                                               | 1.0                     | 1.0     | 1.0          |
| b) Clay lumps                                                                                                                     | 1.0                     | 1.0     | 1.0          |
| c) Materials finer than 75 microns                                                                                                | 1.0                     | 1.0     | 1.0          |
| d) Soft fragments                                                                                                                 | 3.0                     | --      | 3.0          |
| e) Shale                                                                                                                          | --                      | --      | --           |
| f) Total of percentages of all deleterious materials (except mica) including S. No. a) to e) for uncrushed and crushed aggregates | 5.0                     | 2.0     | 2.0          |



### STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 17 of 33  
**Annexure-4**

### **ACCEPTANCE CRITERIA AND PERMISSIBLE LIMITS FOR FINE AGGREGATES AS PER IS 383:2016**

| 4. | Fine aggregates                                                  |                                                                                                                                                     |                        |              |               |
|----|------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|--------------|---------------|
| i) | Physical Tests                                                   | IS Sieve Designation                                                                                                                                | Percentage passing for |              |               |
|    | a) Determination of particle size                                |                                                                                                                                                     | F.A. Zone I            | F.A. Zone II | F.A. Zone III |
|    |                                                                  | 10 mm                                                                                                                                               | 100                    | 100          | 100           |
|    |                                                                  | 4.75 mm                                                                                                                                             | 90-100                 | 90-100       | 90-100        |
|    |                                                                  | 2.36 mm                                                                                                                                             | 60-95                  | 75-100       | 85-100        |
|    |                                                                  | 1.18 mm                                                                                                                                             | 30-70                  | 55-90        | 75-100        |
|    |                                                                  | 600 microns                                                                                                                                         | 15-34                  | 35-59        | 60-79         |
|    |                                                                  | 300 microns                                                                                                                                         | 5 to 20                | 8 to 30      | 12 to 40      |
|    |                                                                  | 150* microns                                                                                                                                        | 0-10                   | 0-10         | 0-10          |
|    | b) Presence of deleterious material                              | Total presence of deleterious materials not to exceed 5% for uncrushed & 2% for crushed/Mixed and manufactured fine aggregates as per Annexure- 4A. |                        |              |               |
|    | c) Soundness Applicable to concrete work subject to frost action | 10% when tested with sodium sulphate and 15% when tested with magnesium sulphate                                                                    |                        |              |               |

\*For crushed stone sands, the permissible limit on 150 micron IS Sieve is increased to 20 percent.



**STANDARD FIELD QUALITY PLAN**

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 18 of 33  
**Annexure-4A**

| Deleterious Substance                                                                                                                                                           | Percentage by Mass, Max |                                                  |              |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|--------------------------------------------------|--------------|
|                                                                                                                                                                                 | Uncrushed               | Crushed/Mixed                                    | Manufactured |
| a) Coal and lignite                                                                                                                                                             | 1.0                     | 1.0                                              | 1.0          |
| b) Clay lumps                                                                                                                                                                   | 1.0                     | 1.0                                              | 1.0          |
| c) Materials finer than 75 microns                                                                                                                                              | 3.0                     | 15.0 (for crushed sand)<br>12.0 (for mixed sand) | 10.0         |
| d) Soft fragments                                                                                                                                                               | --                      | --                                               | --           |
| e) Shale                                                                                                                                                                        | 1.0                     | --                                               | 1.0          |
| f) Total of percentages of all deleterious materials (except mica) including S. No. a) to e) for uncrushed aggregates and a) & b) for crushed/mixed and manufactured aggregates | 5.0                     | 2.0                                              | 2.0          |



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 19 of 33  
**Annexure-5**


### ACCEPTANCE CRITERIA AND PERMISSIBLE LIMITS FOR CONCRETE WORK

|    |          |                         |                                                                                                                                                                                                                                                                                                                            |
|----|----------|-------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1) | Concrete | a) Workability          | Slump shall be recorded by slump cone method, and it shall be between 25-75 mm depending upon workability requirement as per IS 456: Reaffirmed 2021.                                                                                                                                                                      |
|    |          | b) Compressive strength | <b>For nominal (volumetric) concrete mixes compressive strength for 1:1.5:3 (Cement: Fine aggregates: Coarse aggregates) concrete 28 days strength shall be min 265Kg/cm<sup>2</sup> and for 1:2:4 (Cement: Fine Aggregate: Coarse Aggregate) nominal mix concrete 28 days strength shall be min 210Kg/cm<sup>2</sup>.</b> |

**Notes:**

**1) ACCEPTANCE CRITERIA BASED ON 28 DAYS COMPRESSIVE STRENGTHS FOR NOMINAL MIX CONCRETE: As per clause 5.4.10.4 of CPWD Specifications, Volume 1**

- (a) The average of the strength of three specimens be accepted as the compressive strength of the concrete provided the strength of any individual cube shall neither be less than 70% nor higher than 130% of the specified strength.
- (b) If the strength of any individual cube exceeds more than 30% of the specified strength, it will be restricted to 130% only for computation of strength.
- (c) If the actual average strength of accepted sample is equal to or higher than specified strength up to 30% then strength of the concrete shall be considered in order and the concrete shall be accepted at full rates.
- (d) If the actual average strength of accepted sample is less than specified strength but not less than 70% of the specified strength, the concrete may be accepted at reduced rate.-
- (e) In case cube strength is less than 70% of specified strength, then structure shall be rejected (to be dismantled and recast) and thus no payment shall be made.  
If, however the Engineer-in-Charge so desires, on critical/ urgent work, additional tests such as UPV, RHT, Core etc. shall be done at the cost of contractor in consultation with FQA to ascertain the quality of casted concrete. On the basis of proposal of site, FQA shall put up their recommendations to Regional-Head regarding acceptance /non-acceptance of concrete based on test results. Regional head shall take further decision on nonaccepted works whether the said concrete structure to be retained (with / without strengthening measures) or rejected (to be dismantled and recast).



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 20 of 33

If strengthening measures are chosen, a strengthening proposal with detailed reasons / justification for not rejecting the concrete shall be submitted to CC -Engg. CC, Engg will review the strengthening proposal and communicate their approval or revised drawing accordingly.

If structures are retained after strengthening/ rectification measures, All the charges in connection with these additional tests and /or strengthening / rectification work shall be borne by the contractor.

In case such structure is retained, part payment shall be paid as indicated in payment procedure.

2) 53 Grade cement shall be used after obtaining specific approval of the Engineer in charge.

3) Portland slag cement conforming to IS 455: 2015 may be used as per Technical Specification.

4) All Design Mix concrete shall be as per IS 456: 2000, Reaffirmed 2021

5) ACCEPTANCE CRITERIA BASED ON 28 DAYS COMPRESSIVE STRENGTHS FOR DESIGN MIX CONCRETE: As per Table-11 of IS 456, reaffirmed 2021 as given below:

**Table 11 Characteristic Compressive Strength Compliance Requirement**  
(Clauses 16.1 and 16.3)

| Specified Grade | Mean of the Group of 4 Non-Overlapping Consecutive Test Results in $N/mm^2$                                                                                         | Individual Test Results in $N/mm^2$ |
|-----------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------|
| (1)             | Min<br>(2)                                                                                                                                                          | Min<br>(3)                          |
| M 15 and above  | $\geq f_{ck} + 0.825 \times \text{established standard deviation}$<br>(rounded off to nearest $0.5 N/mm^2$ )<br>or<br>$f_{ck} + 3 N/mm^2$ ,<br>whichever is greater | $\geq f_{ck} - 3 N/mm^2$            |

### NOTES

1. In the absence of established value of standard deviation, the values given in Table 8 may be assumed, and attempt should be made to obtain results of 30 samples as early as possible to establish the value of standard deviation.

2. For concrete of quantity up to  $30 m^3$  (where the number of samples to be taken is less than four as per the frequency of sampling given in 15.2.2), the mean of test results of all such samples shall be  $f_{ck} + 4 N/mm^2$ , minimum and the requirement of minimum individual test results shall be  $f_{ck} - 2 N/mm^2$ , minimum. However, when the number of sample is only one as per 15.2.2, the requirement shall be  $f_{ck} + 4 N/mm^2$ , minimum.

6) The test results of the sample shall be the average of the strength of the three specimens. The individual variation shall not be more than  $\pm 15\%$  of the average.



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 21 of 33

### **Annexure- 6** **(Sheet 01 of 02)**

## **SAMPLING PLAN FOR BRICK-WORK**

Scale of sampling and permissible number of defectives for visual and dimensional characteristics.

| No of Bricks in the lot | For characteristics specified for individual bricks |                                            | For Dimensional characteristics for group of 20 bricks- No of bricks to be selected |
|-------------------------|-----------------------------------------------------|--------------------------------------------|-------------------------------------------------------------------------------------|
|                         | No of bricks to be selected                         | Permissible no of defective in the sample. |                                                                                     |
| (1)                     | (2)                                                 | (3)                                        | (4)                                                                                 |
| 2001-10000              | 20                                                  | 1                                          | 40                                                                                  |
| 10001-35000             | 32                                                  | 2                                          | 60                                                                                  |
| 35001-50000             | 50                                                  | 3                                          | 80                                                                                  |

**Note: For a particular work where less than 5000 nos. of bricks are to be used, only visual checks are to be done.**

Scale of sampling for physical characteristics

| Lot size    | Sampling size for compressive strength water absorption and efflorescence | Permissible No of defectives for efflorescence |
|-------------|---------------------------------------------------------------------------|------------------------------------------------|
| (1)         | (2)                                                                       | (3)                                            |
| 2001-10000  | 5                                                                         | 0                                              |
| 10001-35000 | 10                                                                        | 0                                              |
| 35001-50000 | 15                                                                        | 1                                              |



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 22 of 33

### **Annexure- 6** **(Sheet 02 of 02)**

#### **ACCEPTABLE CRITERIA FOR BRICK WORK**

Dimensional Tolerances: The dimensions of modular/ Non modular bricks when tested shall be within the following limits per 20 bricks.

| S.No | DESCRIPTION | MODULAR BRICKS                  | NON-MODULAR BRICKS             |
|------|-------------|---------------------------------|--------------------------------|
| 1    | LENGTH      | 372 to 388 cm ( $380 \pm 8$ cm) | 432 to 468 cm ( $450 \pm 18$ ) |
| 2    | WIDTH       | 176 to 184 cm ( $180 \pm$ cm)   | 213 to 231cm ( $222 \pm 9$ )   |
| 3    | HEIGHT      | 176 to 184 cm ( $180 \pm 4$ cm) | 134 to 146 cm ( $140 \pm 6$ )  |

2) Compressive strength: the bricks shall have a minimum average compressive strength as specified in POWERGRID specification. The compressive strength of any individual brick tested shall not fall below the min. average compressive strength specified for the corresponding class of brick by more than 20%. In case compressive strength of any individual brick tested exceeds the upper limit specified for the corresponding class of bricks, the same shall be limited to upper limit of the class as specified for the purpose of calculating the average compressive strength.

3) Water absorption: The average water absorption of bricks shall not be more than 20% by weight.

4) Efflorescence: The rating of efflorescence of bricks shall not be more than moderate.



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 23 of 33

### **Annexure- 7**

**TABLE – I: SAMPLING FREQUENCY FOR BARDED WIRE**

| S.No. | NUMBER OF REELS IN THE LOT | NO. OF REELS TO BE SELECTED FOR SAMPLING |
|-------|----------------------------|------------------------------------------|
| 1.    | UPTO 25                    | 3                                        |
| 2.    | 26 TO 50                   | 4                                        |
| 3.    | 51 TO 150                  | 5                                        |
| 4.    | 151 TO 300                 | 7                                        |
| 5.    | 301 AND ABOVE              | 10                                       |

**TABLE – II: ACCEPTABLE TENSILE PROPERTIES AS PER IS 278:2009**

| S. NO. | SIZE OF LINE WIRE (MM) | TENSILE STRENGTH<br>OF LINE WIRE<br>N/SQ.MM | MINIMUM BREAKING LOAD OF COMPLETED<br>BARBED WIRE (KN) |
|--------|------------------------|---------------------------------------------|--------------------------------------------------------|
| 1.     | 2.50                   | 390 TO 590                                  | 3.7                                                    |
| 2.     | 2.24                   | 390 TO 590                                  | 3.0                                                    |



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 24 of 33

### Annexure-8

Page 1 of 2

### PHYSICAL, REQUIREMENT OF COARSE AGGREGATE

| S. No. | Type of Construction. | Type of W.B.M.                                                                | Test Method                                                                                                                                                       | Requirements                      |
|--------|-----------------------|-------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------|
| 1.     | Sub-base              | Los Angeles Abrasion Value or Aggregate Impact value                          | IS: 2386:1963, Reaffirmed 2021(Part.IV)<br>IS: 2386:1963, Reaffirmed 2021(Part.IV)<br>IS: 5640:1970, Reaffirmed 2022***                                           | 60% max.<br>*50% max              |
| 2.     | Base                  | a) Los Angeles Abrasion Value or Aggregate Impact value<br>b) Flakiness Index | IS: 2386:1963, Reaffirmed 2021(Part.IV)<br>IS: 2386:1963, Reaffirmed 2021(Part.IV)<br>IS: 5640:1970, Reaffirmed 2022***<br>IS: 2386:1963, Reaffirmed 2021 (PartI) | 50% max.<br>*40% max<br>**15% max |
| 3.     | Surface Course        | a) Los Angeles Abrasion Value or Aggregate Impact value<br>b) Flakiness Index | IS: 2386:1963, Reaffirmed 2021(Part.IV)<br>IS: 2386:1963, Reaffirmed 2021(Part.IV))<br>IS: 2386:1963, Reaffirmed 2021 (PartI)                                     | 40% max.<br>30% max<br>15% max    |
| 4      | Binding Material      | Plasticity index                                                              | IS :2720:1983, reaffirmed 2020 (Part V)                                                                                                                           | Less than 6                       |

\* Aggregates may satisfy requirements of either of the two tests

\*\* The requirements of flakiness index shall be enforced only in case of crushed/broken stone and crushed slag.

\*\*\* Aggregates like brick metal, kankar and laterite which get softened in presence of water, shall be tested for impact value under wet conditions in accordance with IS:5640:1970, Reaffirmed 2022



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 25 of 33  
**Annexure-8**  
**Page 2 of 2**

### GRADING REQUIREMENTS OF COARSE AGGREGATE FOR W.B.M

| Grading No. | Size Range                                                                                          | Sieve designation                          | % by weight passing the sieve         |
|-------------|-----------------------------------------------------------------------------------------------------|--------------------------------------------|---------------------------------------|
| 1           | 90mm to 45mm<br>(Suitable for sub base courses of compacted layer of not less than 90mm thickness). | 125mm<br>90mm<br>63mm<br>45mm<br>22.4mm    | 100<br>90-100<br>25-60<br>0-15<br>0-5 |
| 2.          | 63mm to 45mm                                                                                        | 90mm<br>63mm<br>53mm<br>45mm<br>22.4mm     | 100<br>90-100<br>25-75<br>0-15<br>0-5 |
| 3.          | 53mm to 22.4mm                                                                                      | 63mm<br>53mm<br>45mm<br>22.4mm<br>11.2mm   | 100<br>95-100<br>65-90<br>0-10<br>0-5 |
| 4           | Screening                                                                                           |                                            |                                       |
|             | A) 13.2 mm                                                                                          | 13.2 mm<br>11.2 mm<br>5.6 mm<br>180 micron | 100<br>95-100<br>15-35<br>0-10        |
|             | B) 11.2 mm                                                                                          | 11.2 mm<br>5.6 mm<br>180 micron            | 100<br>90-100<br>15-35                |



### STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 26 of 33

### **Annexure-9**

ACCEPTANCE CRITERIA AND PERMISSIBLE LIMITS FOR ALUMINIUM SECTIONS AS PER IS: 733:1983, reaffirmed 2022 & IS 1285-2023

| S. No. | Name of the test                                                                   | Acceptable limits as per IS 1285-2023                                    |
|--------|------------------------------------------------------------------------------------|--------------------------------------------------------------------------|
| i)     | <b>Chemical analysis test</b>                                                      | 0.40 – 0.90 Percent                                                      |
|        | Magnesium (Mg)                                                                     |                                                                          |
|        | Silicon (Si)                                                                       | 0.30 – 0.70 Percent                                                      |
|        | Manganese (Mn)                                                                     | 0.30 Percent maximum                                                     |
|        | Iron (Fe)                                                                          | 0.60 Percent maximum                                                     |
|        | Copper (Cu)                                                                        | 0.10 Percent maximum                                                     |
|        | Zinc (Zn)                                                                          | 0.20 Percent maximum                                                     |
|        | Titanium                                                                           | 0.20 Percent maximum                                                     |
|        | Chromium                                                                           | 0.10 Percent maximum                                                     |
|        | Aluminum                                                                           | Reminder                                                                 |
| ii)    | <b>Physical tests (For Designation 63400 &amp; Condition/Temper 'W')</b>           |                                                                          |
|        | a) Tensile Strength                                                                | 140.00 MPa Minimum                                                       |
|        | b) 0.2% of proof stress/ Yield stress                                              | 80.00 MPa Minimum                                                        |
|        | c) Elongation percent on 50mm                                                      | 14.0 % Minimum                                                           |
| iii)   | Thickness of the finished Anodic/polyester powder coating measured by micron meter | Shall not be less than 50 micron nor more than 120 microns at any point. |



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 27 of 33

### General Notes:

- 1) This FQP has been prepared for smaller works awarded by the regions. In case of larger works such as Township, buildings etc., this FQP shall hold good, however, the testing frequency of cement, reinforcement steel, Coarse aggregate, Fine aggregates shall be as per Switchyard Civil works SFQP.
- 2) This standard Field Quality Plan is not to limit the supervisory checks which are otherwise required to be carried out during execution of work as per drawings/Technical specifications etc.
- 3) Contractor shall be responsible for implementing/documenting the SFQP. Documents shall be handed over by the contractor to POWERGRID after the completion of the work.
- 4) Project in charge means over all in charge of work. Site in-charge means in-charge of the line. Site engineer means in -charge of the section.  
Site Engineer's responsibility may be allocated to Site JE, with the approval of Regional Head, only in such cases where, Site Engineer is not in position.
- 5) In case of deviation the approving authority will be one step above the officer designated for acceptance in this quality plan subject to minimum level of Line in charge.
- 6) Acceptance criteria and permissible limits for tests are indicated in the Annexures. However, for further details/tests POWERGRID specification and latest relevant Indian standards shall be referred.
- 7) Tests as mentioned in this FQP shall generally be followed. However, E.I.C. reserves the right to order additional tests wherever required necessary at the cost of the agency.
- 8) All counter checks/tests by POWERGRID shall be carried out by POWERGRID's officials' at least at the level of Site Engineer.
- 9) The authorized dealer of reinforcement steel means the dealer whose names are listed in the steel producer's web site or certified by the producers.
- 10) Accepting Authority for testing Laboratory shall be Regional Head.
- 11) READYMIX CONCRETE (RMC) IS ACCEPTABLE FOR USE. HOWEVER, SITE INCHARGE SHALL APPROVE THE SOURCE OF MATERIALS TO BE USED FOR RMC. The documentation to be maintained shall be as per IS 4926:2003, reaffirmed 2022 i.e.
  - i) Information to be supplied by the purchaser (clause 7)
  - ii) Information to be supplied by the producer (clause 8)
  - iii) Sampling for concrete strength should be one set of 3 nos. of cubes for every 50 cum or part thereof for each day of concreting and 28 days compressive strength shall be tested in line with IS 456:2000, reaffirmed 2021.
- 12) Epoxy coating on reinforcement steel wherever required shall be done as per IS 13620:1993, reaffirmed 2020.



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 28 of 33

- 12) Cement is to be used in the order; it is delivered (i.e. First in First Out). In case the cement remains in storage for more than 3 months, the cement shall be retested before use and shall be rejected, if it fails to conform to any of the requirements given in the relevant Indian Standard. Cement shall be packed in bags and stored in accordance with the provisions in IS 4082:1996, reaffirmed 2018.
- 13) If e-mail facility is not available in POWERGRID approved Lab, report may be collected directly by POWERGRID/ Speed Post / Registered Post / UPC.
- 14) In case any Laboratory refuses to allow POWERGRID representative to witness the test, same shall be taken in writing and approval by Regional Head.
- 15) Standard marking of ISI mark along with license number (Seven-digit no., represented as CM/L-----) should be verified for construction materials and test certificate submitted for review
- 16) The mix design shall be made in line with standard format (Annexure) for required grade of concrete and approval of mix design shall be done in consultation with the Regional engineering department.
- 17) Tolerance of cement weight shall be governed by clause no. 10.1.1 of IS 269:2015 for OPC and by clause no. 10.1.1 of IS 1489:2015 (Part 1) for PPC.
- 18) Digital Photographs during concreting, erection and stringing for each location shall be taken and kept in record for future reference by high resolution GPS enabled camera.
- 19) All the charges in connection with NDT/ Core tests shall be borne by the contractor.
- 20) The preference shall be given to batching/RMC plants approved by Quality Council of India.
- 21) The cube testing in in-house Cube testing machine shall be carried out by POWERGRID employee not directly associated with construction activities. The employees associated with O&M works should be preferred for carried out cube test.
- 22) i) For NDT/Core tests results, if not meeting the acceptance criteria, Regional Head is the Accepting Authority.  
ii) CGM (Projects) will be the accepting authority for NDT (UPV & RHT) and core testing done on failed concrete cube test results or not meeting the acceptance criteria in a third party approved lab as per SOP Revision 01 and test results are found satisfactory or meet the acceptance criteria laid down in IS codes. A quarterly report in this regard will be submitted to Regional ED.



# STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 29 of 33  
Annexure-10

## CONCRETE MIX PROPORTIONING-MIX DESIGN

| S. No. | Design Stipulations                                                           | Specified Criteria for Mix Proportion |                      |                      |                      |                      |                      |
|--------|-------------------------------------------------------------------------------|---------------------------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| A      | CONCRETE DETAILS:                                                             | M20                                   | M25                  | M30                  | M35                  | M40                  |                      |
| 1.     | Grade of Concrete (M 20 to M 60- 28 days compressive Strength of 150mm cubes) | <input type="text"/>                  | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> |                      |
| 2.     | Type of Concrete- Structural Classification                                   | PCC                                   | RCC                  | PSC                  | Others               |                      |                      |
|        |                                                                               | <input type="text"/>                  | <input type="text"/> | <input type="text"/> | <input type="text"/> |                      |                      |
| 3.     | Placing Conditions of Concrete (Structural Elements)                          | Building TL                           | Pile                 | S/S Pile             | S/S Structure        | Road                 |                      |
|        |                                                                               | <input type="text"/>                  | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> |                      |
| B      | MIX DESIGN LIMITS: *                                                          | 0.30                                  | 0.35                 | 0.40                 | 0.45                 | 0.50                 | Others               |
| 4.     | Max. Water-Cement Ratio (W/C)- Optional                                       | <input type="text"/>                  | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> |
| 5.     | Min Cement Content- Optional- Kg/m3*                                          | 300                                   | 320                  | 340                  | 360                  | 380                  | Others               |
|        |                                                                               | <input type="text"/>                  | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> |
| C      | EXPOSURE CONDITIONS: @                                                        | Mild                                  | Mod.                 | Severe               | V. Severe            | Extreme              |                      |
| 6.     | Type of Environmental Exposure                                                | <input type="text"/>                  | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> |                      |
| 7.     | Whether Exposed to Sulphate attack from Soil, Water & Containment.            | Yes                                   | No                   | Not Known            |                      |                      |                      |
|        |                                                                               | <input type="text"/>                  | <input type="text"/> | <input type="text"/> |                      |                      |                      |
| 8.     | Whether Exposed to Chloride attack from Soil, Water & Containment.            | Yes                                   | No                   | Not Known            |                      |                      |                      |
|        |                                                                               | <input type="text"/>                  | <input type="text"/> | <input type="text"/> |                      |                      |                      |



# STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 30 of 33

|     |                                                                                                   |                              |                      |                      |                      |                      |                      |
|-----|---------------------------------------------------------------------------------------------------|------------------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| D   | CONCRETE INGREDIENTS:                                                                             | Ground                       | River                | Pond                 | Others               |                      |                      |
| 9.  | Source of Water for Construction                                                                  | <input type="text"/>         | <input type="text"/> | <input type="text"/> | <input type="text"/> |                      |                      |
| 10. | Type of Cement & Strength Grade.                                                                  | OPC<br>Gr.33                 | OPC<br>Gr.43         | OPC<br>Gr.53         | PPC<br>BFS           | PPC<br>FAB           | PSC                  |
|     |                                                                                                   | <input type="text"/>         | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> |
| 11. | Brand, Batch No./Week/Year of Cement<br>(Test Certificate to be sent to Lab)                      | <input type="text"/>         | <input type="text"/> |                      |                      |                      |                      |
| 12. | Cementitious Materials Proposed for<br>Improvement of Density &<br>Permeability.                  | Micro silica/<br>Silica Fume | Slag                 | Fly Ash              | Other<br>Pozzolana   |                      |                      |
|     |                                                                                                   | <input type="text"/>         | <input type="text"/> | <input type="text"/> | <input type="text"/> |                      |                      |
| 13. | FRESH CONCRETE Properties:<br>Desired Slump of Concrete (mm)#                                     | 25-55                        | 25-75                | 100-150              | Others               |                      |                      |
|     |                                                                                                   | <input type="text"/>         | <input type="text"/> | <input type="text"/> | <input type="text"/> |                      |                      |
| 14. | QUALITY CONTROL AT SITE:<br>Degree of Quality Control at Project<br>Site (For Standard Deviation) | V.Good                       | Good                 | Fair                 | Std.Lab.             |                      |                      |
|     |                                                                                                   | <input type="text"/>         | <input type="text"/> | <input type="text"/> | <input type="text"/> |                      |                      |
| 15. | Max. Size of Coarse Aggregate (MSA)-<br>mm                                                        | 63                           | 40                   | 20                   | 12.5                 | 4.75                 | Other                |
|     |                                                                                                   | <input type="text"/>         | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> | <input type="text"/> |
| 16. | Source of Coarse Aggregate                                                                        | Name of Quarry               |                      |                      |                      | Location             |                      |
| 17. | Type of Fine Aggregate                                                                            | River<br>Sand                | Crushed<br>Sand      | Others<br>Specify    |                      |                      |                      |
|     |                                                                                                   | <input type="text"/>         | <input type="text"/> | <input type="text"/> |                      |                      |                      |
| 18. | Source of Fine Aggregate (Sand)                                                                   | Name of Quarry               |                      |                      |                      | Location             |                      |
| 19. | Admixture proposed to be Used (Batch                                                              | Brand Name:                  |                      |                      |                      | Batch No.:           |                      |



## STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 31 of 33

|     |                                                            |                                                                                                                                                                                                                                                                        |
|-----|------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|     | MTC to be Submitted to Lab)                                |                                                                                                                                                                                                                                                                        |
| 20. | Type of Compaction Equipment                               | <div> <div>Plate Vibrator</div> <input type="checkbox"/> </div> <div> <div>Needle Vibrator</div> <input type="checkbox"/> </div> <div> <div>Vibro Hyd. Pressure</div> <input type="checkbox"/> </div> <div> <div>Piling Concrete</div> <input type="checkbox"/> </div> |
| 21. | Type of Concrete Placement Facility at Project             | <div> <div>Manual Lift</div> <input type="checkbox"/> </div> <div> <div>Hudraulic Bucket</div> <input type="checkbox"/> </div> <div> <div>Concrete Pump</div> <input type="checkbox"/> </div>                                                                          |
| 22  | Maximum/Minimum temp. envisaged during placing of concrete |                                                                                                                                                                                                                                                                        |

\* Minimum Cement Content, Maximum Water-Cement Ratio and Minimum Grade of Concrete for Different Exposures with Normal Weight Aggregates of 20 mm Nominal Maximum Size- Reinforced Concrete

|  | Minimum cement content Kg/m3 | Maximum free water cement ration | Minimum grade of concrete |
|--|------------------------------|----------------------------------|---------------------------|
|  | 300                          | 0.55                             | M20                       |
|  | 300                          | 0.5                              | M25                       |
|  | 320                          | 0.45                             | M30                       |
|  | 340                          | 0.45                             | M35                       |
|  | 360                          | 0.4                              | M40                       |

# Slump Value as per SFQP.

- i. For Switchyard civil works – 25 to 75mm
- ii. For Switchyard pile foundations- 150-180mm
- iii. For Transmission line open cast foundations- 25 to 75mm
- iv. For Transmission line pile foundations- 150-180mm



@EXPOSURE CONDITIONS

### STANDARD FIELD QUALITY PLAN

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 32 of 33

| ENVIRONMENT | EXPOSURE CONDITIONS                                                                                                                                                                                                                                                                           |
|-------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| MILD        | <ul style="list-style-type: none"><li>• Concrete surfaces protected against weather or aggressive</li></ul>                                                                                                                                                                                   |
| MODERATE    | <ul style="list-style-type: none"><li>• Concrete exposed to condensation and rain</li><li>• Concrete continuously under water</li><li>• Concrete surfaces sheltered from rain or freezing whilst wet</li><li>• Concrete in contact or buried under non-aggressive soil/ground water</li></ul> |
| SEVERE      | <ul style="list-style-type: none"><li>• Concrete surfaces exposed to severe rain, alternate wetting and drying or occasional freezing whilst wet or severe condensation</li><li>• Concrete completely immersed in sea water</li><li>• Concrete exposed to coastal environment</li></ul>       |
| VERY SEVERE | <ul style="list-style-type: none"><li>• Concrete surfaces exposed to sea water spray, corrosive fumes or severe freezing conditions whilst wet.</li><li>• Concrete in contact with or buried under aggressive subsoil/ ground water</li></ul>                                                 |
| EXTREME     | <ul style="list-style-type: none"><li>• Surface of members in tidal zone, Members in direct contact with liquid/solid aggressive chemicals</li></ul>                                                                                                                                          |



**STANDARD FIELD QUALITY PLAN**

|               |                                                  |
|---------------|--------------------------------------------------|
| Item          | Civil Works for Site Packages (up to Rs 15 Lacs) |
| Applicability | POWERGRID Projects                               |
| Date of Issue | 10.07.2024                                       |
| Validity      | Till next revision                               |

|          |                                       |
|----------|---------------------------------------|
| SFQP No. | DOC No.: C/FQA/SFQP/SITE-M-CIVIL-2020 |
| REV.     | 01                                    |

Page 33 of 33

**Annexure-11**

**Standard procedure for Testing/Assessment of compressive strength of cast Concrete  
(Revision-I) issued vide  
IOM No: CC: FQA: SOP:2024 dated 05-07-2024**





पावर ग्रिड कॉर्पोरेशन आफ इंडिया लिमिटेड  
कारपोरेट एफ. क्यू.ए. विभाग  
अंतर कार्यालय ज्ञापन

प्रेषक: मुख्य महाप्रबंधक, एफ. क्यू.ए.  
केंद्रीय कार्यालय

सेवा में : As per Distribution

संदर्भ संख्या: CC:FQA:SOP:2024

दिनांक: 05-07-2024

**विषय:** Revised (Revision 1) Standard procedure for Testing / Assessment of compressive strength of cast Concrete for nominal and design mix.

Please find enclosed herewith the Revised (Revision 1-SOP) Standard procedure for Testing / Assessment of compressive strength of cast Concrete, duly approved by competent authority. These guidelines are being issued both for nominal mix and design mix concrete. Henceforth, this standard operating procedure (Revision 1-SOP Annexure I) shall be applicable for all future projects of POWERGRID.

This issues with the approval of the Competent Authority.

Encl: Revision 1-SOP Annexure I (08 pages)

एम अशोक कुमार  
05/07/2024  
(एम अशोक कुमार)

**वितरण/Distribution:**

- कार्यपालक निदेशक :** उत्तरी क्षेत्र-1/उत्तरी क्षेत्र-2/उत्तरी क्षेत्र-3 /पश्चिमी क्षेत्र-1/पश्चिमी क्षेत्र-2/ दक्षिण क्षेत्र-1/दक्षिण क्षेत्र-2/ पूर्वी क्षेत्र-1 /पूर्वी क्षेत्र-2/ उत्तर पूर्वी क्षेत्र/ Arunachal comprehensive T&D/एन. ई. आर.पी.एस. आई. पी./ ओड़िसा प्रोजेक्ट्स./टी.बी.सी.बी./ उप मुख्य सतर्कता अधिकारी/संविदा सेवाए/ अभियांत्रिकी /अभियांत्रिकी एच वी डी सी / एफ. क्यू.ए.
- ES/PS of CMD/Director (Projects)/Director (Operation)/Director (Fin)/CVO
- समस्त एफ. क्यू.ए. कार्यपालक

**Standard procedure for Testing/Assessment of compressive strength of cast Concrete**

**Structural Elements**

(A) Foundation shall be divided into two structural elements:

- a) Foundation Pad(s)
- b) Chimney/Column

(B) Pile foundation shall be divided into three structural elements:

- a) Piles
- b) Pile cap (s)
- c) Pedestal
- d) Tie Beam

(C) Building shall be divided into four structural elements:

- a) Foundation pad(s)
- b) Column
- c) Beam
- d) Slab

(D) Miscellaneous infrastructure works - cable trench, Fire wall, Boundary wall Panels, RCC roads , RCC drains

## **1.0 Acceptance Criteria:**

For all RCC structures (such as Foundation Pad, Pile Cap & Pedestal, Roads/Drains/ Column / Chimney/ Cable Trenches/ Firewall/ Boundary wall panels, Beams, Columns & Slabs of Buildings.

### **1.1 Nominal Mix:**

#### **(i) Acceptance of Concrete Cubes test results**

If test results of Concrete cubes & Cores are in between 70%-100% of specified grade of concrete, CPWD specifications Cl.no.5.4.10.4, Vol 1 shall be followed. Accordingly, the following may be adopted to consider the acceptance criteria of nominal mix concrete.

- (a) The average of the strength of three (3) specimen be accepted as the compressive strength of the concrete provided the strength of any individual cube shall neither be less than 70% nor higher than 130% of the specified strength.
- (b) If the strength of any individual cube exceeds more than 30% of specified strength, it will be restricted to 130% only for computation of strength.
- (c) If the actual average strength of accepted sample is equal to or higher than specified strength up to 30% then strength of the concrete shall be considered in order and the concrete shall be accepted at full rates.
- (d) If the actual average strength of accepted sample is less than specified strength but not less than 70% of the specified strength, the concrete may be accepted at reduced rate. No NDT such as UPV & RHT etc. shall be carried out.
- (e) In case cube strength is less than 70% of specified strength, then structure shall be rejected (to be dismantled and recast) and thus no payment shall be made.

If, however the Engineer-in-Charge so desires, on critical/ urgent work, additional tests such as UPV, RHT, Core etc. shall be done at the cost of contractor in consultation with FQA to ascertain the quality of cast concrete. On the basis of proposal of site, FQA shall put up their recommendations to Regional-Head regarding acceptance /non-acceptance of concrete based on test results. Regional head shall take further decision on non-accepted works whether the said concrete structure to be retained (with / without strengthening measures) or rejected (to be dismantled and recast).

If strengthening measures are chosen, a strengthening proposal with detailed reasons / justification for not rejecting the concrete shall be submitted to CC -Engg. CC-Engg. will review the strengthening proposal and communicate their approval or revised drawing accordingly.

If structures are retained after strengthening/ rectification measures, All the charges in connection with these additional tests and /or strengthening / rectification work shall be borne by the contractor.

In case such structure is retained, part payment shall be paid as indicated in the payment procedure.

#### **(ii) Acceptance of Core test results:**

In case of nominal mix, Acceptance of Concrete Core test results (In case of doubt/strength



is less than 70% of specified strength/concrete cube test results not available).

Core test shall be carried out in case of doubt regarding desired compressive strength of concrete used either due to poor workmanship or based on results of cube strength tests/cube test results are not available.

The acceptability criteria adopted for concrete cube test results of Nominal Mix may also be applicable for Core test results.

## 1.2 Design mix: Concrete Cubes

Acceptable Compressive strength:- Acceptance of Concrete Cube test results considering average value of three specimens.

a) when mean of the group of four (4) non overlapping consecutive test results:  
 $\geq f_{ck} + 0.825 \times \text{established standard deviation (rounded off to nearest } 0.5 \text{ N/mm}^2)$   
or  
 $f_{ck} + 3 \text{ N/mm}^2$

whichever is greater for M 15 and above and Individual test results minimum  $\geq f_{ck} - 3 \text{ N/mm}^2$

### Notes:

- i) In the absence of established value of standard deviation, the values given in Table -8 in IS 456-2000 may be assumed, and attempt should be made to obtain results of 30 samples as early as possible to establish the value of standard deviation.
- ii) For concrete quantity up to 30 m<sup>3</sup> (where number of samples to be taken is less than four (4) as per the frequency of sampling given in 15.2.2 of IS 456:2000), the mean test results of all such samples shall be  $f_{ck} + 4 \text{ N/mm}^2$ , minimum and the requirement of minimum individuals test results shall be  $f_{ck} - 2 \text{ N/mm}^2$ , minimum. However, when number of sample is only one as per 15.2.2 IS 456:2000, the requirement shall be  $f_{ck} + 4 \text{ N/mm}^2$ , minimum.

In case cube strength is as per above, then full payment shall be released.

- b) when compressive strength value is in between  $f_{ck}$  and  $f_{ck} + 4/f_{ck} + 3$  as applicable, then the payment shall be made as indicated in the payment procedure. No NDT such as UPV & RHT etc. shall be carried out.
- c) However, in invalid results cases, if there are no further samples available, the average of two (2) closest values may be considered for determination of compressive strength as per IS 516 (Part I/Sec I) 2021. The payment shall be made as indicated in the payment procedure.
- d) In cases, compressive strength is less than  $f_{ck}$  and acceptance criteria brought out above, the structure shall be rejected.

If, however the Engineer-in-Charge so desires, on critical/ urgent work, additional tests such as UPV, RHT, Core etc. shall be done at the cost of contractor in consultation with FQA to ascertain the quality of cast concrete. On the basis of proposal of site, FQA shall put up their recommendations to Regional-Head regarding acceptance/non-acceptance of concrete



based on test results. Regional head shall take further decision on non-accepted works whether the said concrete structure to be retained (with / without strengthening measures) or rejected (to be dismantled and recast).

If strengthening measures are chosen, a strengthening proposal with detailed reasons / justification for not rejecting the concrete shall be submitted to CC -Engg. CC- Engg. will review the strengthening proposal and communicate their approval or revised drawing accordingly.

If structures are retained after strengthening/ rectification measures, All the charges in connection with these additional tests and /or strengthening / rectification work shall be borne by the contractor.

In case such structure is retained, part payment shall be paid as indicated in payment procedure.

**1.3 Design Mix Concrete Core Test: - Acceptance of concrete core test results:(In case of doubt/If strength is less than Fck/ Concrete cube test results are not available)**

Core test shall be carried out in case of doubt regarding strength of concrete used either due to poor workmanship or based on results of cube strength tests or less than fck (Characteristic cube compressive strength of concrete)/Concrete cube test results are not available.

If Average value of core specimens is 85% of the specified Grade of concrete and no individual value is less than 75% of the specified Grade of concrete and the same is considered acceptable as per B-2.5.1 IS 516(Part4):2018.

Any compressive strength deviation from the above, the acceptance/rejection procedure has been elaborated in Payment procedure.

- 1.4** No NDT (RH & UPV testing) test is required if concrete cube strength found in between 70% to 100 % for nominal mix and in between FCK and FCK+3/FCK+4 (as applicable) for design mix. However, If applicable, the NDT (UPV & RH testing) test is to be carried out and accepted as per latest IS 516 (Part-5, Sec-1)/516 (Part-5, Sec-4).

**2.0 Payment Procedure:**

For all RCC structures (such as Foundation Pad, Pile Cap & Pedestal, Roads/Drains/ Column / Chimney/ Cable Trenches/ Firewall/ Boundary wall panels, Beams, Columns & Slabs of Buildings)

**2.1 Payment Procedure (Other than Pile): In case of Nominal Mix**

For Concrete Cubes and Cores (Core shall be extracted in case of doubt/If specified strength is less than 70%, in average and individual/ Concrete cube test results are not available)

Acceptable Compressive strength- As per specified strength of concrete.

- a) when Concrete cube or core strength equal or more than specified strength of Concrete, Full payment shall be applicable



- b) when Concrete cube or core strength lies in between 70-100% of the specified strength of Concrete then payment shall be released on prorata basis for concrete portion and full payment shall be made on other components such as excavation, PCC, Reinforcement steel, Shuttering as applicable.
- c) when Concrete cube or core strength is less than 70% of specified strength of Concrete, the Engineer-in-Charge shall reject the defective portion of work represented by sample and no payment shall be made for the rejected work inclusive of concrete, reinforcement steel, PCC, excavation etc.
- d) If, however the Engineer-in-Charge so desires, on critical/ urgent work, additional tests such as UPV, RHT, Core etc. shall be done at the cost of contractor in consultation with FQA to ascertain the quality of cast concrete. On the basis of proposal of site, FQA shall put up their recommendations to Regional-Head regarding acceptance /non-acceptance of concrete based on test results. Regional head shall take further decision on nonaccepted works whether the said concrete structure to be retained (with / without strengthening measures) or rejected (to be dismantled and recast).

If strengthening measures are chosen, a strengthening proposal with detailed reasons / justification for not rejecting the concrete shall be submitted to CC-Engg. CC-Engg. will review the strengthening proposal. and communicate their approval or revised drawing accordingly.

If structures are retained after strengthening/ rectification measures, All the charges in connection with these additional tests and /or strengthening / rectification work shall be borne by the contractor.

In case such structure is retained, no payment shall be made for concreting & full payment of other components such as excavation, PCC, Reinforcement steel, shuttering if applicable as per original approved drawing/BOQ shall be made.


## **2.2 Payment procedure (Other than Pile) in case of Design Mix: Concrete Cubes**

- a) when mean of the group of four (4) non overlapping consecutive test results:  
 $\geq f_{ck} + 0.825 \times \text{established standard deviation (rounded off to nearest } 0.5 \text{ N/mm}^2)$   
or  
 $f_{ck} + 3 \text{ N/mm}^2$

whichever is greater for M 15 and above and Individual test results minimum  $\geq f_{ck} - 3 \text{ N/mm}^2$

### **Notes:**

- i) In the absence of established value of standard deviation, the values given in Table -8 in IS 456-2000 may be assumed, and attempt should be made to obtain results of 30 samples as early as possible to establish the value of standard deviation.
- ii) For concrete quantity up to 30 m<sup>3</sup> (where number of samples to be taken is less than four (4) as per the frequency of sampling given in 15.2.2 (Table 11) of IS 456:2000), the mean test results of all such samples shall be  $f_{ck} + 4 \text{ N/mm}^2$ , minimum and the requirement of minimum individuals test results shall be  $f_{ck} - 2 \text{ N/mm}^2$ , minimum. However, when number of sample is only one as per 15.2.2 IS 456:2000, the requirement shall be  $f_{ck} + 4 \text{ N/mm}^2$ , minimum.



In case cube strength is as per above, then full payment shall be released.

- b) when compressive strength value is in between  $f_{ck}$  and  $f_{ck}+4/f_{ck}+3$  as applicable, then the payment shall be released on prorata basis for concrete and full payment shall be made towards excavation, PCC, Reinforcement steel, Shuttering as applicable as per drawing/BOQ. No NDT such as UPV & RHT etc shall be carried out.
- c) However, in invalid results cases, if there are no further samples available, the average of two (2) closest values may be considered for determination of compressive strength as per IS 516 (Part I/Sec I) 2021. In such cases when the compressive strength meets the specified strength of Concrete, payment for concrete portion shall be released on prorata basis and full payment on other components such as towards excavation, PCC, Reinforcement steel, Shuttering etc shall be made.
- d) In cases, compressive strength is less than  $f_{ck}$  and acceptance criteria brought out above, the structure shall be rejected.

If, however the Engineer-in-Charge so desires, on critical/ urgent work, additional tests such as UPV, RHT, Core etc. shall be done at the cost of contractor in consultation with FQA to ascertain the quality of cast concrete. On the basis of proposal of site, FQA shall put up their recommendations to Regional-Head regarding acceptance /non-acceptance of concrete based on test results. Regional head shall take further decision on non-accepted works whether the said concrete structure to be retained (with / without strengthening measures) or rejected (to be dismantled and recast).

If strengthening measures are chosen, a strengthening proposal with detailed reasons / justification for not rejecting the concrete shall be submitted to CC -Engg. CC, Engg. will review the strengthening proposal and communicate their approval or revised drawing accordingly.

If structures are retained after strengthening/ rectification measures, All the charges in connection with these additional tests and /or strengthening / rectification work shall be borne by the contractor.


In case such structure is retained, no payment shall be made for concreting & full payment of other components such as excavation, PCC, Reinforcement steel, shuttering if applicable as per original approved drawing/BOQ shall be made.

### **2.3 Payment procedure (Other than Pile) in case of Design Mix: Concrete Cores**

Concrete Cores (Core shall be extracted In case of doubt/If specified strength is less than  $f_{ck}$ , Concrete cube test results are not available)

The payment procedure for core test results is detailed below:

- i) When equivalent cube strength is equal/more than  $f_{ck}+4/f_{ck}+3$  as applicable, then full payment shall be made.
- ii) When equivalent cube strength is in between  $f_{ck}$  and  $f_{ck}+4/f_{ck}+3$  as applicable/When equivalent cube strength is in between 85%  $f_{ck}$  and no individual value is less than 75% of the specified Grade of concrete, the same is considered acceptable, prorata payment for concrete portion and full payment shall be made on other components such as excavation, PCC, Reinforcement steel, Shuttering as applicable.



- iii) In case equivalent cube strength is less than 85%fck and/or an individual core has a strength less than 75%, then structure shall be rejected and thus no payment shall be made.

If, however the Engineer-in-Charge so desires, on critical/ urgent work, additional tests such as UPV, RHT, Core etc. shall be done at the cost of contractor in consultation with FQA to ascertain the quality of cast concrete. On the basis of proposal of site, FQA shall put up their recommendations to Regional-Head regarding acceptance /non-acceptance of concrete based on test results. Regional head shall take further decision on nonaccepted works whether the said concrete structure to be retained (with / without strengthening measures) or rejected (to be dismantled and recast).

If strengthening measures are chosen, a strengthening proposal with detailed reasons / justification for not rejecting the concrete shall be submitted to CC -Engg. CC, Engg. will review the strengthening proposal. and communicate their approval or revised drawing accordingly.


If structures are retained after strengthening/ rectification measures, All the charges in connection with these additional tests and /or strengthening / rectification work shall be borne by the contractor.

In case such structure is retained, no payment shall be made for concreting & full payment of other components such as excavation, PCC, Reinforcement steel, shuttering if applicable as per original approved drawing/BOQ shall be made.

### 3.0 Acceptance Criteria & Payment procedure for Pile Foundations (Design Mix)

- (i) In case of Pile foundation, when value of Average cube strength is  $fck + 0.825 \times \text{Standard Deviation}$  or  $fck + 4/fck + 3$  as applicable whichever higher, then Full payment shall be applicable.
- (ii) when value of Average cube strength is equal to or more than  $fck$  but less than  $fck + 0.825 \times \text{Standard Deviation}$  or  $fck + 4/fck + 3$  as applicable which ever greater, then payment shall be released on prorata basis for concrete portion and full payment shall be made to all other components such as boring, SPT, Reinforcement steel, MS Liner, as applicable as per drawing/BOQ.
- (iii) However, in invalid result cases, if there is no further samples available, the average of two (2) closest values may be considered for determination of compressive strength as per IS 516 (Part 1/Sec 1) 2021. In such cases when the compressive strength meets the specified strength of Concrete, payment for concrete portion shall be released on prorata basis and full payment on other components such as towards boring, Reinforcement steel, MS Liner, SPT etc as applicable shall be made.
- (iv) In case compressive strength of cubes observed is less than  $fck$ , Vertical load test (routine test) shall be carried out in Pile foundations of Switchyard / Transmission lines wherever applicable in consultation with Engineering to ascertain the capacity of pile as per IS 2911(Part IV). If the test result is meeting the codal requirement, then 50 % payment shall be made for concrete & full payment shall be made towards Boring, Reinforcement steel, SPT, MS Liner as applicable in line with original approved drawings/BOQ.

Alternatively, for Transmission Line cases, if Head of the Region so desires, the proposal may be examined by Engineering for acceptance after carrying out suitable remedial measures including strengthening/ OR if structures are retained after due approval from



(v) If compressive strength of cube of piles observed is less than  $f_{ck}$  & not technically meeting /cleared by Engineering as brought out above, the structure shall be rejected and then no payment shall be paid for the rejected pile inclusive of concrete, boring, reinforcement steel, MS Liner etc.

- i) In case only one set of cube results are available for a location and results are found to be less than 70% of specified strength in case of Nominal Mix, all four legs of the location shall be analyzed as per the procedure as indicated in acceptance criteria.
- ii) However, in case of locations where two or more set of cube results are available and results are found less than 70% of specified strength, in case of Nominal mix, then only one pit shall be excavated at a time (utmost care shall be taken to avoid any damage to concrete surface or disturb undercut zones of foundation) and analyzed those legs as per the procedure as indicated in acceptance criteria.
- iii) The calibration certificate of the rebound hammer should be checked before commencement of a test.
- iv) NDT (UPV & Rebound Hammer Test) or Core Test shall be conducted by POWERGRID approved laboratory. The lab shall be entrusted to carry out the testing which shall be witnessed by Site/FQA executive. The laboratory shall submit the report containing the UPV & Rebound Hammer Test or CoreTest results along with the field data.
- v) Acceptance criteria of construction materials shall be as per SFQP/relevant IS codes.
- vi) For core testing at least three specimens are required as per IS:516(Part-4). While extracting cores, four to five specimens may be taken from the foundation pads (uniformly distributed) such that three sound specimen may be used for testing. Otherwise repeat test shall be made. If cores of sufficient length cannot be extracted for testing due to poor quality of concreting/workmanship etc. as per IS: 516(Part-4), the foundation shall be treated as rejected.
- vii) When core test is carried out, technical acceptance and commercial implications shall be governed solely on the basis of core test results. This shall be applicable for both nominal and design mix concrete.
- viii) For additional structures/piles if any installed in lieu of rejected structure/pile, no payment shall be made for the rejected pile and the additional pile shall be dealt as per the provisions of Contract.
- ix) Generally, Core test should not be repeated after completion and availability of test reports for the same structure of the same batch of concrete.
- x) No core extraction/test is permitted in case of pile foundations
- xi) The provision of additional 5% Core testing as mentioned in SFQP's stands deleted.

