

BOM FOR PAINTING OF BOUNDARY WALL AL 400/220 kV AMRITSAR SUBSTATION.

| Sl. No. | DSR-2021 | SAP Service Code | DESCRIPTION OF ITEMS  | SAC    | GST | Unit | Total Quantity |
|---------|----------|------------------|---|--------|-----|------|----------------|
| 1       | 13.112   |                  | Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade  |        |     |      |                |
| a       | 13.112.1 | 120003290        | Old work (Two or more coats applied @ 1.43 ltr/ 10 sqm) over existing cement paint surface  | 995419 | 18% | Sqm  | 8477.10        |
| 2       | 13.91    | 120001600        | Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete   | 995419 | 18% | Sqm  | 6350.00        |
| 3       | 13.80    | 120001511        | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.   | 995472 | 18% | Sqm  | 1100.00        |
| 4       | 14.1     |                  | Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In-Charge. |        |     |      |                |
| a       | 14.1.1   | 120001523        | With cement mortar 1:4 (1 cement : 4 fine sand)   | 995419 | 18% | Sqm  | 1000.00        |