

PRE-BID CLARIFICATION

Name Of Tender : Supply, Installation, Testing, Commissioning of NGR Bypass arrangement to use switchable Line Reactor as Bus Reactor at 765KV Chikaluripeta Substation under PSITSU project

Tender Reference No: SR-/C&M/I-2486/2022/IFB/
RFx No:5002002157

Sr. No	Clause No	Page No	As per PGCIL Specification	Queries/Clarification of the bidder	POWERGRID Replies to Queries
1	Bill of Materials- Sl. No.- 6	1	Fabrication,galvanizing and supply of 24mm Dia foundation bolts including nuts,check nuts,washers and pack plates. Foundation bolts 24MM Quantity- 32 Each	Do we have to supply foundation bolts for 145 kV BPI or PGCIL requires as a spare. Additionally, as per Bill Of Materials -Sl. No.-2, foundation bolts has to be supplied along with 145 kV BPI. Please clarify.	Supply of Foundation bolts is the part of supply of 145kV BPI. Supply of foundation bolts has to be provided prior to the civil works
2	08. Scope of work & special conditions: SECTION-I: GENERAL INFORMATION AND SCOPE OF WORK- 1) The scope of work includes: 1.d	1	Integration of the NGR bypass scheme in the existing CRP & ALSTOM SCADA at Chikaluripeta and in NTAMC is also in the scope of the contractor.	Do we have to considering only hardwiring or software part as well for SCADA- NTAMC integration. We request PGCIL to keep in OEM-ALSTOM scope for the said work.	It is not included in BOQ & hence excluded from the scope of Contractor
3	Bill of Materials- Sl. No.- 4 and 08. Scope of work & special conditions: SECTION-I: GENERAL INFORMATION AND SCOPE OF WORK- 1) The scope of work includes: 1.i	1	Supply of Power and control cables.	Since CT is not part of scope of work nor in BOQ, do we have to consider cables for CT.	Cables for CT not required. However cables supply & laying for CB has to be considered.
4	08. Scope of work & special conditions: 3. INSPECTION	3	Main Items like 145 Circuit Breaker, BPI offered will be inspected at manufacturers/Suppliers premises by POWERGRID QA&I representative or any other POWERGRID representative nominated by competent authority. However POWERGRID reserved the right to waive off the inspection at factory. Necessary dispatch clearance shall be obtained before dispatch of the equipment.	Do we have to consider inspection for terminal connectors, earthing items, PVC pipes, steel structures and obtain CIP/MICC.	The Inspection shall be carried out as per specification/ TS

रंजित

संतोष कुमार अय्यम/Santhosh Kumar Artham
 उप महानिरीक्षक (सू.उ.सा) / Deputy General Manager (C&M)
 पावरग्रिड, द.क्ष.प्र./ POWERGRID, SRTS-I
 सिकंदराबाद / Secunderabad-500 080