



पावर ग्रिड कोर्पोरेशन ऑफ इंडिया लिमिटेड
Power Grid Corporation of India Limited
सूचना का अधिकार अभिनियम 2005 के अंतर्गत केन्द्रीय लोक सूचना अधिकारी
Central Public Information Officer under the RTI Act, 2005
केन्द्रीय कार्यालय, 'सौदामिनी', प्लॉट नं.2, सेक्टर-29, गुडगांव, हरियाणा-122007
Corporate Centre, 'Saudamini', Plot No. 2, Sector-29, Gurgaon, Haryana-122007



CP/RTI/2018/67

Date: 25th May, 2018

Shri Liyit Panor,
Village - Panggo,
PO- Tuting,
Arunachal Pradesh

Sub: Information under Right to Information Act, 2005.

Sir,

This has reference to your RTI request dated 08.04.18 forwarded by CPIO, NERTS to CPIO,CC, POWERGRID through letter dated 1st May, 2018, under RTI Act, 2005. Point wise reply to the queries are given below:

Point No. 1 & 2

Available information is attached as **Annexure-I**.

Point No. 3 & 4

Revised Cost Estimate is under approval.

Point No. 5

Available information is attached as **Annexure-II**.

Point No 6

Not applicable

First Appeal, if any, against the reply of CPIO may be made to the first appellate Authority within 30 days of the receipt of the reply of CPIO. Details of Appellate Authority at Corporate Centre, Gurgaon, under RTI Act, 2005 is as below:

Shri Sanjeev Singh,
Executive Director (CMG) & Appellate Authority
Corporate Centre, Power Grid Corporation of India Limited
"Saudamini", Plot No. 2, Sector-29, Gurgaon – 122007, Haryana.
Email ID: sanjeev@powergridindia.com
Phone No. 0124-2571962

Thanking you,

भवदीय,

(अजय होलानी)

अपर महाप्रबंधक (के.आ.) एवं के.लो.सू.अधिकारी

Email ID: cpio.cc@powergrid.co.in

Copy to : **Shri Pranjit Deka,**
CPIO & DGM (PESM)
NERTS, Power Grid Corporation of India Ltd.
Dongtiah, Lower Nongrah, Lapalang
Shillong – 793 001

PROJ: Comprehensive Scheme of T&D in Arunachal Pradesh			
PART -A- TRANSMISSION SYSTEM			
S.NO.	DESCRIPTION	LINE 24	LINE 25
		TRANSMISSION LINE : ALONG - YINKIYONG 132KV S/C LINE (ON D/C TOWER)	TRANSMISSION LINE : YINKIONG - TUTING 132KV S/C LINE (ON D/C TOWER)
		100 KM	125 KM
1	Tower Steel	1705.56	2342.41
2	Conductor	464.28	579.94
3	Earthwire	0.00	0.00
4	Insulator	108.19	146.65
5	Hardware Fittings	42.87	59.40
6	Conductor & E'wire Accessories	26.69	36.84
	Sub-Total - Supply Cost	2347.59	3165.24
7	Freight, Insurance & Taxes	213.19	287.75
8	Entry Tax	0.00	0.00
9	Service Tax	0.00	0.00
9	Erection	308.28	423.22
10	Stringing	343.50	429.37
11	Civil Works	1811.61	2553.57
	Sub-Total	5024.17	6859.15
	Equipment Cost per Km	50.24	54.87
12	River crossing pile foundation & Aviation	0.00	0.00
	Total Equipment Cost	5024.17	6859.15
	Cost per Km	50.24	54.87
	Preliminary & Gen. Civil Works	2111.05	2715.62
	Total Cost	7135.22	9574.77
	Total Cost per Km	71.35	76.60

COST BREAK UP OF TRANSMISSION LINE

PROJ: COMPREHENSIVE SCHEME FOR STRENGTHENING OF TRANS. SYSTEM IN NER & SIKKIM			ANNEXURE - 1.2.25(A)								
STATE: ARUNACHAL PRADESH - REV DPR											
TRANSMISSION LINE : YINKHONG - TUTING-132KV SIC LINE (ON D/C TOWER)											
Line Length : 125 Km.											
Sr. No.	Description	Unit	Quantity	SPARES		TOTAL	F & I @ 8%	CST @ 2%	Entry Tax @ 0.0%	Ere/Civill Works	TOTAL
				Total	Quantity						
			6=4x5	7	8=7x5	9=6+8	10	11	12	13=9+10+11+12	
Wind Zone 5			50 m/s	TERRAIN	Hilly Terrain						
Egpt Exworks Incl. Excise Duty											
No.	Description	Unit	Quantity	Rate (Rs.)	Total	Quantity	Total	Total	Total	Total	Total
6.1.3	Repair Sleeve for Conductor	Nos.	71	5	355		355				355
6.1.4	Flexible Copper Bond for earthwire	Nos.	4,982	692	3,448		3,448				3,448
6.1.5	Vibration Damper For Conductor	Nos.		581	0		0				0
6.1.6	Vibration Damper for earthwire	Nos.			0		0				0
6.1.7	Bundle Spacer for earthwire	Nos.			0		0				0
6.1.8	Rigid Spacer for Conductor	Nos.			0		0				0
6.1.9	Earthwire Tension Clamps	Nos.		738	0		0				0
6.1.10	Earthwire-Suspension Clamps	Nos.		738	0		0				0
6.1.11	T - Connector	Nos.	0	1,678	0		0				0
Type test charges for C & E accessories			LS		0		0				0
Sub Total					3,803		3,803				3,803
7.0	Tower Erection	MT	2,883	14,680	42,322		42,322				42,322
Normal towers											
Sub Total					42,322		42,322				42,322
8.0	Foundations										
8.1	Excavations										
Normal Dry soil											
Normal Wet soil											
Dry Fissured Rock			Cu.M.	13,712	336		336				336
Wet Fissured Rock			Cu.M.	1,037	371		371				371
Hard Rock			Cu.M.	16,841	1,053		1,053				1,053
Concreting			Cu.M.	94	3,197		3,197				3,197
Concreting 1:1.5:3(M20)			Cu.M.	4,447	15,709		15,709				15,709
Reinforcement			Cu.M.	565	14,136		14,136				14,136
Sub Total			MT	372	116,419		116,419				116,419
9.0	Benching										
All kinds of soil except HR & FR											
Fissured Rock			Cu.M.	40,250	418		418				418
Hard Rock			Cu.M.	40,250	995		995				995
Sub Total			Cu.M.	5	1,490		1,490				1,490
10.0	Revetment										
Sub Total					168.25		168.25				168.25
					400.49		400.49				400.49
Sub Total					568.84		568.84				568.84

COST BREAK UP OF TRANSMISSION LINE

PROJ: COMPREHENSIVE SCHEME FOR STRENGTHENING OF TRANS. SYSTEM IN NER & SIKKIM		ANNEXURE - 1.2.25(A)										
STATE: ARUNACHAL PRADESH - REV DPR		PART - A- TRANSMISSION SYSTEM										
TRANSMISSION LINE: YINKIONG - TUTING 132KV S/C LINE (ON D/C TOWER)		(Rs. in Lakhs)										
Line Length: 125 Km.		TERRAIN: Hilly Terrain										
Wind Zone 5: 50 m/s												
Sr. No.	Description	Egpt Exworks incl. Excise Duty		S P A R E S		TOTAL Exw & Spares	F & I @ 8% CST @ 2%	Entry Tax @	Ere/Civil Works	TOTAL		
		Unit	Quantity	Rate (Rs.)	Total						Quantity	Total
1	2	3	4	5	6=4x5	7	8=7x5	11	12	13=9+10+11+12		
i)	Random Rubble Stone	Cu.M.	4,500	8,483			9=6+8		381.74	381.74		
	Masonry including excavation											
ii)	Stone bound in galvanised wire netting, including excavation	Cu.M.	500	8,074					40.37	40.37		
iii)	Backfilling and leveling of Volumes enclosed in revetment	Cu.M.	6,000	443					26.58	26.58		
iv)	M-15(1:2:4) Concrete for top seal cover of revetment	Cu.M.	10	18,944					1.89	1.89		
Sub Total					0.00	0.00	0.00	0.00	450.58	450.58		
10.0	Stringing-132KV S/C (normal)	K.M.	125	343,498					429.37	429.37		
15.0	Detail Survey including route alignment, profiling & tower spotting	K.M.	125	37,869					47.34	47.34		
	Check survey	KM	125	24,094					30.12	30.12		
16.0	Soil Investigation in											
	All kinds of soil except HR & FR	Loc.	15	22,083					3.31	3.31		
	Fissured rock	Loc.	15	48,909					7.34	7.34		
	Hard rock	Loc.	5	84,837					4.24	4.24		
Transmission Line Total					311065		5459	316524	28775	0.00	340616	6185915

COST BREAK UP OF TRANSMISSION LINE

PROJ:	COMPREHENSIVE SCHEME FOR STRENGTHENING OF TRANS. SYSTEM IN NER & SIKKIM	ANNEXURE - 1.2.24 (A)	
STATE:	ARUNACHAL PRADESH - REV DPR		
TRANSMISSION LINE:	ALONG - YINKIYONG 132KV SIC LINE (ON D/C TOWER)		
Line Length: 100 Km.			
Sr. No.	Description	Unit	Rate (Rs.)
PART - A - TRANSMISSION SYSTEM			
TERRAIN: Hilly Terrain			
Wind Zone 5: 50 m/s			
SPARES			
Egpt Exworks Incl. Excise Duty		Total	Quantity
6=4x5		7	8=7x5
9=6+8		10	11
TOTAL Exw & Spares		12	13=9+10+11+12
TOTAL F & I @ 8%		14	15
CST @ 2%		16	17
Entry Tax @		18	19
Ere/Civil Works		20	21
TOTAL		22	23
(Rs. in Lakhs)			
1.0	TOWER STEEL		
1.1	High Tensile Steel	MT	626
1.2	Mild Steel	MT	1,371
1.3	Hexagonal bolts & Nuts	MT	103
1.4	Antitheft bolts & Nuts	MT	103
1.5	Tower Accessories & Earthing	LS	
1.6	Proto Assembly charges for tower	LS	
2.0	Conductor		
2.1	ACSR "PANTHER"	K.M.	305
	Type test charges for conductor	LS	
3.0	Earthwire		
3.1	Earthwire (G.S. 7/3.15mm)	K.M.	
	Type test charges for earthwire	LS	
4.0	Insulator		
4.1	Insulator (70 KN Standard)	Nos.	19,888
4.2	Insulator (90 KN Standard)	Nos.	19,888
	Type test charges for insulator	LS	
5.0	Hardware Fitting		
5.1	Single Suspension 'I' Fittings	Set	
5.2	Single-Suspension pilot Fittings	Set	
5.3	Single Tension Fittings	Set	
5.4	Double Tension Fittings	Set	
	Type test charges for hardware fittings.	LS	
6.1	Conductor & E'wire Accessories		
6.1.1	MSCJ For Conductor	Nos.	189
6.1.2	MSCJ For Earthwire	Nos.	189

Sr.	No.	Description	Unit	Quantity	Rate (Rs.)	Egpt Exwks Incl. Excise Duty		Total	Quantity	Total	TERRAIN	Hilly Terrain	ANNEXURE - 1.2.24 (A)
						6=4x5	5						
COST BREAK UP OF TRANSMISSION LINE													
PROJECT: COMPREHENSIVE SCHEME FOR STRENGTHENING OF TRANS. SYSTEM IN NER & SIKKIM													
STATE: ARUNACHAL PRADESH - REV DPR													
TRANSMISSION LINE: ALONG - YINKIYONG 132KV S/C LINE (ON D/C TOWER)													
Line Length: 100 Km.													
PART - A - TRANSMISSION SYSTEM													
Wind Zone 5 50 m/s													
SPARES													
TOTAL													
Exw & Spares 9=6+8													
F & T @ 8%													
CST @ 2%													
10													
Entry Tax @ 0.0%													
11													
Works 12													
13=9+10+11+12													
6.1.3	2	Repair Sleeve for Conductor	3	4	5								
6.1.4		Flexible Copper Bond for earthwire	Nos.	57									
6.1.5		Vibration Damper For Conductor	Nos.	3,588	692			0.00	0.00	0.00			
6.1.6		Vibration Damper for Earthwire	Nos.		581			24.83	0.00	0.00			
6.1.7		Rigid Spacer for Conductor	Nos.					0.00	0.00	0.00			
6.1.8		Earthwire-Tension Clamps	Nos.					0.00	0.00	0.00			
6.1.9		Earthwire Suspension Clamps	Nos.		738			0.00	0.00	0.00			
6.1.10		T - Connector	Nos.	0	738			0.00	0.00	0.00			
6.1.11		Type test charges for C & E accessories	Nos.	0	1,678			0.00	0.00	0.00			
6.1.12		Sub Total	LS					26,662	0.00	0.00			
7.0		Tower Erection	MT	2,100	14,680				0.00	0.00			
7.0.1		J Normal towers											
7.0.2		Sub Total											
8.0		Foundations											
8.1		Excavations											
8.1.1		Normal Dry soil											
8.1.2		Normal Wet soil	Cu.M.	6,681	336								
8.1.3		Dry Fissured Rock	Cu.M.		371								
8.1.4		Wet Fissured Rock	Cu.M.	15,202	1,053								
8.1.5		Hard Rock	Cu.M.		1,101								
8.1.6		Concreting	Cu.M.	45	3,197								
8.1.7		Concreting 1:1.5:3(M20)	Cu.M.	3,292	15,709								
8.1.8		Reinforcement 1:3:6	Cu.M.	421	14,136								
8.1.9		Sub Total	MT	271	116,419								
9.0		Benching											
9.0.1		All kinds of soil except HR & FR											
9.0.2		Fissured Rock	Cu.M.	51,750	418								
9.0.3		Hard Rock	Cu.M.	10,350	995								
9.0.4		Sub Total	Cu.M.	3,000	1,990								
10.0		Revetment											
10.0.1													
10.0.2													
10.0.3													
10.0.4													
10.0.5													
10.0.6													
10.0.7													
10.0.8													
10.0.9													
10.0.10													

PROJ: COMPREHENSIVE SCHEME FOR STRENGTHENING OF TRANS. SYSTEM IN NER & SIKKIM		PART - A- TRANSMISSION SYSTEM		TERRAIN		S P A R E S		TOTAL		Ere/Civil		TOTAL	
STATE: ARUNACHAL PRADESH - REV DPR		Wind Zone 5 50 m/s		Hilly Terrain		TOTAL Exw & Spares		Ere/Civil		Works		TOTAL	
TRANSMISSION LINE: ALONG - YINKYONG 132KV SIC LINE (ON D/C TOWER)		Line Length: 100 Km.		TERRAIN		TOTAL		Ere/Civil		Works		TOTAL	
Sr. No.	Description	Unit	Quantity	Rate (Rs.)	Total	Quantity	Total	F & I @ 8%	Entry Tax @	CST @ 2%	11	0.0%	TOTAL
1	Random Rubble Stone	Cu.M.	3,500	8,483	29,691	7	58,485	10	11	12	12	13=9+10+11+12	296.91
i)	Masonry including excavation including excavation	Cu.M.	100	8,074	807.4								8.07
ii)	Backfilling and leveling of	Cu.M.	4,000	443	1,772								17.72
iii)	Volumes enclosed in reevment	Cu.M.	10	18,944	189.44								1.89
iv)	M-15(1:2:4) Concrete for top seal cover of reevment	Cu.M.	10	18,944	189.44								1.89
Sub Total													324.59
10.0	Stringing 132KV SIC (normal)	K.M.	100	343,498	34,349.8								343.50
15.0	Detail Survey including route alignment, profiling & tower spotting	K.M.	15	37,869	568.035								5.68
	Check survey	KM	100	24,094	2,409.4								24.09
16.0	Soil investigation in	Loc.	3	22,083	66.249								0.66
	All kinds of soil except HR & FR	Loc.	3	48,909	146.727								1.47
	Fissured rock	Loc.	0	84,837	0.00								0.00
	Hard rock	Loc.	0	84,837	0.00								0.00
Transmission line Total													5,024.17

ANNEXURE - 1.1
All figures in Rs. Lakhs

ABSTRACT COST ESTIMATE
PRELIMINARY & GENERAL CIVIL WORKS

PROJ: **COMPREHENSIVE SCHEME FOR STRENGTHENING OF TRANSMISSION & DISTRIBUTION SYSTEM IN ARUNACHAL PRADESH**
ARUNACHAL PRADESH - REVISED DPR -JULY 2013

Sr.	Line/Sub station	Survey & Soil Investigation	Crop & PTCC compensation	Forest compensation incl. NPV	Colony	Total Cost
A.	Transmission Line					
	ARUNACHAL PRADESH					
24.0	ALONG-YINGKIONG 132KV S/C Line (ON D/C TOWER)	25.00	300.00	1786.05		2111.05
25.0	YINGKIONG - TUTING 132KV S/C Line (ON D/C TOWER)	31.25	362.50	2321.87		2715.62

Electronic Tender Opening Event® (E-TOE)

View - Comparison Chart based on ElectronicForms™

? Page Help

This is the content pertaining Reports Guidelines

View - Comparison Chart based on ElectronicForms™

Sallent Details of Tender

Tender Search Code (TSC)	PG-2015-TN000452
Buyer's Tender Reference Number (B-TRN)	CC-CS/165-NER/TW-3302/3/G4
TOE Reference	TOE-1
Date and Time of Start of TOE	08-Feb-2016 11:30:00 RTZ
Type of TOE	Public Online TOE

Details of Bid

Bid-Part	Technical-Part
Bid-Type	Base-Single
ElectronicForms™ - Outline of requirements	Simple Text

Comparison Chart Section-1

	Bidder-1	Bidder-2	Bidder-3
Organization ID	ETS-IN-2012-RS0000006 (KEC International Limited)	ETS-IN-2012-RS0000008 (KALPATARU POWER TRANSMISSION LTD)	ETS-IN-2012-RS0000009 (TATA PROJECTS LIMITED)
Tower Package TW08 for: (i) 132kV S/C on D/C tower Along - Yingklong (ii) 132kV S/C on D/C tower Yingklong - Tuting			
Bidder's Name	KEC INTERNATIONAL LIMITED	KALPATARU POWER TRANSMISSION LTD	TATA PROJECTS LIMITED

Comparison Chart Section-2

Base Requirements Tower Package TW08 for: (i) 132kV S/C on D/C tower Along - Yingklong (ii) 132kV S/C on D/C tower Yingklong - Tuting

Base-Bid

	Bidder-1	Bidder-2	Bidder-3
Organization ID	ETS-IN-2012-RS0000006 (KEC International Limited)	ETS-IN-2012-RS0000008 (KALPATARU POWER TRANSMISSION LTD)	ETS-IN-2012-RS0000009 (TATA PROJECTS LIMITED)
1. Integrity Pact Details	Yes	Yes	Yes
2. Bid Security Details			
2(a) Submitted	Yes	Yes	Yes
2(b) Bid Security Number	017751618G000016	359301GL0000616	200162016
2(c) Issued By (Name of Bank)	ALLAHABAD BANK	UBI GANDHINAGAR	Indian Overseas Bank
2(d) Bid Security Amount	23394000 (Indian Rupee)	23394000 (Indian Rupee)	23394000 (Indian Rupee)
2(e) Valid upto	30-Sep-2016	17-Oct-2016	30-Sep-2016
3. SAFETY PACT	Yes	Yes	Yes

Comparison Chart Section-3

	Bidder-1	Bidder-2	Bidder-3
Organization ID	ETS-IN-2012-RS0000006 (KEC International Limited)	ETS-IN-2012-RS0000008 (KALPATARU POWER TRANSMISSION LTD)	ETS-IN-2012-RS0000009 (TATA PROJECTS LIMITED)
1. AUTHORISED SIGNATORY (Sole Bidder/ Lead Partner of JV)			
1(a) Name	NITIN GUPTA	D MARUTHI PRASAD	Mr. Abhik Pal & Mr Rabi Ratna Patel
1(b) Designation	SR. MANAGER - MKTG & BD	SR VICE PRESIDENT MKTG	AVP & Head-BD & AVP & Head-Engg.
1(c) Address	8TH FLOOR, BUILDING NO. 9A, DLF CYBER CITY, PHASE - III, GURGAON 122002	101, PART-III, GIDC ESTATE, SECTOR-28, GANDHINAGAR-382028, GUJARAT	TATA PROJECTS LIMITED Ground Floor, Tower-B, Green Boulevard, Plot No. B-9A, Sector-62 Noida Uttar Pradesh India 201307
2. AUTHORISED SIGNATORY (Other Partner of JV) (If Bidder is JV)			
2(a) Name	Field Not Filled	Field Not Filled	NA
2(b) Designation	Field Not Filled	Field Not Filled	NA
2(c) Address	Field Not Filled	Field Not Filled	NA

Print

Close

Export to Excel

ElectronicTender Opening Event® (E-TOE)

View - Comparison Chart based on ElectronicForms™

Page Help

This is the content pertaining Reports Guidelines

View - Comparison Chart based on ElectronicForms™

Sallent Details of Tender

Tender Search Code (TSC)	PG-2015-TN000452
Buyer's Tender Reference Number (B-TRN)	CC-CS/165-NER/TW-3302/3/G4
TOE Reference	TOE-2
Date and Time of Start of TOE	29-Mar-2016 15:30:00 RTZ
Type of TOE	Public Online TOE
Details of Bid	
Bid-Part	Financial-Part
Bid-Type	Base-Single
ElectronicForms™ - Outline of requirements	Simple Text

Comparison Chart Section-1

	Bidder-1	Bidder-2	Bidder-3
Organization ID	ETS-IN-2012-RS0000006 (KEC International Limited)	ETS-IN-2012-RS0000008 (KALPATARU POWER TRANSMISSION LTD)	ETS-IN-2012-RS0000009 (TATA PROJECTS LIMITED)
Tower Package TW08 for: (i) 132kV S/C on D/C tower Along - Yingklong (ii)132kV S/C on D/C tower Yingklong - Tuting			
Bidder's Name	KEC INTERNATIONAL LIMITED	KALPATARU POWER TRANSMISSION LTD	TATA PROJECTS LIMITED

Comparison Chart Section-2

Base Requirements

Tower Package TW08 for: (i) 132kV S/C on D/C tower Along - Yingklong (ii)132kV S/C on D/C tower Yingklong - Tuting

Base-Bid

	Bidder-1	Bidder-2	Bidder-3
Organization ID	ETS-IN-2012-RS0000006 (KEC International Limited)	ETS-IN-2012-RS0000008 (KALPATARU POWER TRANSMISSION LTD)	ETS-IN-2012-RS0000009 (TATA PROJECTS LIMITED)
1. TOTAL PRICE FOR SCHEDULE NO-1	830306242 (Indian Rupee)	848126832 (Indian Rupee)	756969557.29 (Indian Rupee)
(Ex-works price of Plant and Equipment Including Type Test Charges)			
2. TOTAL PRICE FOR SCHEDULE NO-2	94511780 (Indian Rupee)	154407600.20 (Indian Rupee)	127740733.83 (Indian Rupee)
(Local transportation, Insurance, and other incidental services)			
3. TOTAL PRICE FOR SCHEDULE NO-3	1798029583 (Indian Rupee)	1669851576.80 (Indian Rupee)	1777203829.76 (Indian Rupee)
(Installation Charges)			
4. TOTAL PRICE FOR SCHEDULE NO-4	NOT APPLICABLE	NOT APPLICABLE	NOT APPLICABLE
(Training Charges)			
5. TOTAL PRICE FOR SCHEDULE NO.5	137160428.48 (Indian Rupee)	129838089.48 (Indian Rupee)	61093534.25 (Indian Rupee)
(Taxes and Duties)			
Plus Octroi, Entry Tax , Other Taxes & Duties quoted by bidder at Sl. No. 4,5 & 6 of Sch-5			
6. TOTAL PRICE FOR SCHEDULE NO.7	NOT APPLICABLE	NOT APPLICABLE	NOT APPLICABLE
Break-up of Type Test Charges			
(Total of this Schedule is included in Schedule - 1 above.			
7. GRAND TOTAL [Sch-1+Sch-2+Sch-3+Sch-4+Sch-5]	2860008033.48 (Indian Rupee)	2802224098.48 (Indian Rupee)	2723007655.1 (Indian Rupee)
Plus applicable Octroi, Entry Tax , Other Taxes & Duties			

Comparison Chart Section-3

	Bidder-1	Bidder-2	Bidder-3
Organization ID	ETS-IN-2012-RS0000006 (KEC International Limited)	ETS-IN-2012-RS0000008 (KALPATARU POWER TRANSMISSION LTD)	ETS-IN-2012-RS0000009 (TATA PROJECTS LIMITED)
Bidder's Address (Sole Bidder/ Lead Partner of JV)	8TH FLOOR, BUILDING NO. 9A, DLF CYBER CITY, PHASE - III, GURGAON 122002	101, PART-III, GIDC ESTATE, SECTOR-28, GANDHINAGAR-382028, GUJARAT	TATA PROJECTS LIMITED Ground Floor, Tower-B, Green Boulevard, Plot No. B-9A, Sector-62 Noida Uttar Pradesh India 201307

Print

Close

Export to Excel